



# **ECS** Mid-Atlantic, LLC

Draft Groundwater Management Plan

Briery Creek Farm Site  
6055 Rolling Road South  
Scottsville, Virginia 24590  
ECS Project No. 47:16310-C

July 7, 2023





July 7, 2023

Mr. William D. Fritz, AICP  
Albemarle County  
401 McIntire Road, North Wing  
Charlottesville, Virginia 22902

On behalf of:

Mr. Emerson Grey Prosser  
Sun Communities, Inc.  
27777 Franklin Road, Suite 300  
Southfield, Michigan 48034

ECS Project No. 47:16310-C

Reference: Draft Groundwater Management Plan  
Briery Creek Farm Site  
6055 Rolling Road South, Scottsville, Virginia 24590

Dear Mr. Fritz,

On behalf of our client, Sun Communities, Inc., ECS Mid-Atlantic, LLC (ECS) is pleased to provide this Draft Groundwater Management Plan (GWMP) related to the Briery Creek Farm Site in Scottsville, Virginia. The GWMP is being submitted to satisfy requirements outlined within Article X of the Albemarle County Code and has been written in accordance with Section 2 of the Albemarle County Design Standards Manual for Engineering. If there are any questions regarding this report, or a need for further information, please contact the undersigned at (540) 785-6624.

Respectfully Submitted,

**ECS MID-ATLANTIC, LLC**

Thomas P. Nelson, P.G.  
Principal Hydrogeologist



Michael L. Maloy, P.G.  
Principal Geologist

Draft Groundwater Management Plan  
Briery Creek Farm Site  
6055 Rolling Road South  
Scottsville, Virginia 24590

---

CLIENT

Sun Communities, Inc.  
27777 Franklin Road, Suite 300  
Southfield, Michigan 48034

---

SUBMITTED BY

ECS Mid-Atlantic, LLC  
4004 Hunterstand Court, Suite 102  
Charlottesville, Virginia 22911

---

---

PROJECT

47:16310-C

---

---

DATE

July 7, 2023

---

**Draft Groundwater Management Plan  
Briery Creek Farm Site  
6055 Rolling Road South, Scottsville, Virginia 24590**

1.0	INTRODUCTION .....	1
2.0	SITE SETTING .....	1
2.1	Subject Site Description .....	1
2.2	Topographic and Hydrologic Setting .....	2
2.3	Geology & Hydrogeology .....	2
2.3.1	<i>Geologic Setting</i> .....	2
2.3.2	<i>Hydrogeologic Setting</i> .....	3
3.0	POTENTIAL SOURCES OF CONTAMINATION & GROUNDWATER QUALITY ...	3
3.1	Potential Sources of Contamination .....	3
3.2	Groundwater Quality .....	4
4.0	WELL INSTALLATION, MODIFICATION, AND TESTING ACTIVITIES .....	5
4.1	Red Barn Well .....	6
4.1.1	Red Barn Well Characterization .....	6
4.1.2	Red Barn Well Construction Modification .....	7
4.2	Well A .....	8
4.2.1	Well A Installation .....	8
4.3	Well B .....	8
4.3.1	Well B Installation .....	9
4.3.2	Well B Step-Drawdown Testing .....	9
5.0	WELL INVENTORY .....	10
5.1	Evaluation of Proximal Well Users .....	10
5.2	Proximal Well Record Search .....	11
6.0	GROUNDWATER MANAGEMENT PLAN & CONTINGENCY PLAN .....	11
6.1	Groundwater Management Plan .....	11
6.2	Contingency Plan .....	12
7.0	CLOSING .....	12
8.0	REFERENCES .....	13
9.0	LIMITATIONS .....	13

**FIGURES**

Figure 1	Site Location Map
Figure 2	Site Concept Plan and Supply Well Locations
Figure 3	Site Layout Map
Figure 4	Topographic and Hydrologic Mapping
Figure 5	Geologic Mapping
Figure 6	Estimated Groundwater Recharge and Discharge Zones
Figure 7	Well Locations on Parcels within 1,000 Feet of Subject Site Boundary
Figure 8	Proximal Properties with Available Well Records

**TABLES**

Table 1	Summary of Pavilion Well Sampling Results for Detected Analytes
Table 2	Red Barn Well Step-Drawdown Test Findings (Pre-Modification)
Table 3	Well B Step-Drawdown Test Findings

**APPENDICES**

Appendix A	Water Well Completion Reports & Geologic Well Logs
Appendix B	Red Barn Well & Well B Step-Drawdown Test Data Plots
Appendix C	Wells A & B VDH-ODW Well Site Approval Letter
Appendix D	Information About Properties Located within 1,000 Feet of the Subject Site
Appendix E	Available Well Records of Proximal Offsite Properties

## **1.0 INTRODUCTION**

ECS Mid-Atlantic, LLC (ECS) is pleased to provide this Draft Groundwater Management Plan (GWMP) documenting hydrogeologic conditions and existing supply wells that are planned for use at the Briery Creek Farm Site. The Briery Creek Farm site is located at 6055 Rolling Road South in Scottsville, Virginia and encompasses approximately 724 acres within nine parcels. Five of the nine parcels are located in Fluvanna County while the remaining four parcels are located in Albemarle County. The location of the subject site is shown in Figure 1.

ECS understands that the site's proposed development will include approximately 250 vacation rental cabins and various other amenities that will be serviced by a central water system that will be supplied by groundwater supply wells. The municipal water service area does not extend to the subject site, and as such, groundwater supply wells will be required to meet the potable water needs of the planned development. Peak hourly demand is expected to be 35 gallons per minute (gpm) and the maximum daily demand is expected to be 25,000 gallons per day. A concept plan showing the planned development and the location of the site's planned supply wells is provided as Figure 2.

ECS has completed well siting, installation, modification, and preliminary testing activities at the site. Methodology and findings related to the installation, modification, and testing of the site's planned supply wells is discussed within this Draft GWMP. Additionally, a description of the site setting, a discussion of potential proximal contaminant sources, and a discussion of proximal offsite supply wells is provided herein.

## **2.0 SITE SETTING**

### **2.1 Subject Site Description**

The subject site consists of nine land parcels, four of which are located in Albemarle County and five of which are located in Fluvanna County. Albemarle County parcels are identified as parcel numbers 124-4A, 124-4B, 124-4, and 124-12 and Fluvanna County parcels are identified as parcel numbers 26-A-A37, 26-A-A2, 26-A-A38, 26-A-A5A, and 26-A-3. The combined area of the site is approximately 724 acres. The site is currently used as a wedding venue and as pastureland for cattle. The site is bound to the east by Highway 620. Adjoining properties in the vicinity of the site are primarily undeveloped, agricultural, or low-density residential. A site layout map showing the site boundary and surrounding area is included as Figure 3.

Five bedrock wells are currently present at the subject site, as shown in Figure 3. The Red Barn Well, Pavilion Well, and Cabin Well are active supply wells used by the site's current development and Wells A and B were installed by ECS as part of the groundwater exploration phase of this project. The Red Barn Well provides potable water to the current facility's Red Barn wedding event building located near the site's current entrance. The Pavilion Well provides potable water to the Pavilion structure located near the shore of the site's largest reservoir and equipment sheds located to the east of the well. The Cabin Well provides potable water to two rental cabins located near the southern shore of the site's largest reservoir. Wells A and B were installed by ECS in 2023 in an effort to develop groundwater supply sources. The Red Barn Well and Well B will be used to supply the entire potable demand of the subject site. Well A will not be used as a supply well due to

its low yield and the Pavilion Well and Cabin Well will not be used as supply wells because their constructions do not meet public well construction criteria.

ECS submitted a well record request to the Blue Ridge Health Department for GW-2 Water Well Completion Reports for the site's existing wells, but a record was only available for the Pavilion Well. ECS also spoke with Virginia Department of Health Office of Drinking Water (VDH-ODW) staff who confirmed that none of the site's existing wells were permitted as public wells and that well records were unavailable. The Red Barn Well has since been converted to a public supply well, as discussed in a later subsection of this report. Visual observation of the Cabin Well indicated that the well is a 6-inch diameter drilled well with 6-inch diameter steel casing. The Water Well Completion Report for the Pavilion Well indicated that the well was drilled as a Class IIIB private well in September 2019 to a depth of 420 feet below ground surface (bgs). The diameter of the well is six inches, and the casing consists of 6-inch diameter PVC, which was installed to a depth of 56 feet bgs. The well was grouted to a depth of 50 feet bgs using a bentonite slurry. Water-bearing zones are present at depths of 77–78 feet bgs, 219–221 feet bgs, and 400–401 feet bgs. The static water level within the well is reported to be 40 feet bgs at the time of its installation and the well has a reported yield of 7 gpm. A copy of the Pavilion Well's Water Well Completion Report is included as Appendix A. Water Well Completion Reports for Well A, Well B, and the modified Red Barn Well are also provided within Appendix A and are discussed in further detail in a later subsection of this report.

## 2.2 Topographic and Hydrologic Setting

Ground surface elevation at the site ranges from approximately 410–550 feet above mean sea level (amsl) with a dominant drainage direction toward the west. The highest elevation areas of the site are located along its eastern margin and the lowest elevations are located along the western margin where Briery Creek exits the site. National Hydrography Dataset mapping indicates that several streams and 15 reservoirs are present at the site. The largest perennial stream at the site is Briery Creek, which feeds the site's largest reservoir. A second perennial stream is mapped as being present at the northern portion of the site, which also feeds into the site's largest reservoir. The remaining streams are mapped as being intermittent. A map showing topography and surface water hydrologic mapping at and in the vicinity of the site is included as Figure 4.

## 2.3 Geology & Hydrogeology

### 2.3.1 Geologic Setting

The subject site is located within the Piedmont Physiographic Province, which is characterized by gently rolling topography and weathered bedrock. Geologic mapping at a scale of 1:24,000 by Evans (1994) is available for the northern portion of the site. This mapping indicates that the site is underlain by a Cambrian-age metagraywacke unit comprised primarily of quartz and plagioclase feldspar. Higher-scale geologic mapping of the entire site by the Virginia Division of Mineral Resources (2003) at a scale of 1:500,000 indicates that the entire site and surrounding area is underlain by a single geologic unit comprised of metagraywacke, quartzose schist, and mélange. No faults are mapped as being present at the site and the nearest fault is mapped as being located one mile to the west. Geologic mapping of the site and surrounding area is provided as Figure 5.

Saprolite, which is a soft and generally unconsolidated geologic material formed by the in-situ chemical weathering of underlying bedrock, typically overlies consolidated bedrock in

the Piedmont Province. Saprolite and other unconsolidated sediment are collectively referred to as “overburden”. Overburden thickness is variable and is dependent on several factors, including topography, geologic characteristics, and climate, and was observed to be 40 feet thick at the Well A and B locations.

### 2.3.2 Hydrogeologic Setting

Groundwater flow within crystalline and meta-sedimentary aquifers of the Piedmont Province is primarily via interconnected joints and fractures within the rock, as primary porosity within these units is typically low. Regional fracture density and the degree to which fractures are interconnected can be highly variable and is dependent on several factors, including geologic structure, rock type, and depth. The size, number, and interconnection of fractures typically decreases with depth. Saprolite overlying metasedimentary bedrock typically functions as a source of groundwater storage for bedrock aquifers. As such, wells completed in areas with a thin saprolite layer are typically more likely to be adversely impacted by drought conditions than wells completed in areas with thicker saprolite layers. The degree to which water is transmitted from the saprolite layer to bedrock is largely a function of the degree of fracturing in the uppermost section of bedrock.

ECS reviewed a hydrogeologic assessment study of Albemarle County completed by ENSAT Corporation in 2003. Findings from the ENSAT study indicate that the subject site is located within the Piedmont Proper Hydrogeologic Unit (i.e., Unit VIII). The Piedmont Proper Hydrogeologic Unit is characterized by gently rolling piedmont topography with bedrock comprised primarily of metagraywacke, quartzose schist, and mélange. The ENSAT study classifies each hydrogeologic unit within Albemarle County on the basis of its general groundwater availability, with each unit being assigned either a low, medium, or high groundwater availability. The Piedmont Proper Hydrogeologic Unit is classified as having a low groundwater availability rating. This classification should be considered a general rating, as bedrock well yields are highly dependent on the specific locations at which the wells are drilled and the majority of wells that were used by ENSAT to assign groundwater availability classification ratings would not have been professionally sited to improve the likelihood of obtaining a higher yield.

ECS reviewed National Wetland Inventory wetlands mapping and National Hydrography Dataset surface water mapping to estimate groundwater recharge and discharge zones within the site boundaries, as areas where wetlands and/or surface water are present were assumed to represent groundwater discharge zones and areas where these features are absent were assumed to represent groundwater recharge zones. Of the total site area (723.8 acres), 81.4 acres is estimated to be a groundwater discharge zone and the remaining 642.4 acres is estimated to be a groundwater recharge zone. The estimated groundwater discharge zone represents 11.2% of the total site area. A map showing the estimated groundwater recharge and discharge zones across the site is included as Figure 6.

## **3.0 POTENTIAL SOURCES OF CONTAMINATION & GROUNDWATER QUALITY**

### 3.1 Potential Sources of Contamination

A regulatory database search report provided by Environmental Data Resources, LLC (EDR), was used to assess whether nearby contaminated sites would be likely to pose a



significant risk to groundwater contamination to the subject site. The results of the EDR database search revealed that no sites were mapped or listed in a regulatory database within EDR's default search radius. Portions of the subject site, including at and in the vicinity of Well B, is used as grazing land for free range cattle. Current grazing practices are unlikely to contaminate the site's wells due to the relatively small number of cattle that graze the area (less than 50) and rotating nature by which the cattle graze different fields at the site. Grazing is expected to cease in the vicinity of Well B following site development and the field in which the well is located is expected to be maintained as an open meadow. The Red Barn structure in the vicinity of the Red Barn Well is expected to be used as a maintenance facility. The maintenance facility is located beyond the VDH-ODW-mandated setback zone for Class II public supply wells and chemicals or other equipment that could potentially release contaminants to the subsurface will not be stored within the Class II 50-foot wellhead protection area (WHPA). It is ECS's opinion that current and planned future use of the site is unlikely to cause contamination to the bedrock aquifer that would impact the planned development's proposed supply wells.

Although the location of the site's septic drainfield has not been provided to ECS, we have been informed that its location will not be anywhere in the vicinity of the planned development's supply wells (i.e., the Red Barn Well and Well B). The nearest property boundary to the Red Barn Well is located approximately 260 feet to the north, which is 210 feet beyond the Class II WHPA. The nearest property boundary to Well B is located approximately 520 feet to the north and the nearest structure is located approximately 1,830 feet to the northwest. As such, it is ECS's opinion that onsite and offsite septic drainfields do not pose a significant threat of contamination to the site's planned supply wells.

### 3.2 Groundwater Quality

ECS mobilized to the subject site on August 2, 2022 to collect a water sample from the site's Pavilion Well to better understand the general groundwater chemistry at the site. The Pavilion Well is plumbed with a pressure tank and manifold consisting of a raw water sampling spigot and a pressure switch. An inline sediment filter is present and no other treatment systems were apparent. ECS collected the water sample from the raw water spigot, prior to the water moving through the sediment filter. The well was purged for approximately 30 minutes prior to collecting the sample. The sample was shipped overnight on ice to Pace Analytical in Mt. Juliet, Tennessee for analysis of the following general water quality parameters: volatile organic compounds (VOCs), chlorinated pesticides, nitrate, nitrite, sulfate, metals, hardness, and alkalinity.

Laboratory results indicated that all analytes were below the laboratory's minimum detection limits for drinking water except for the analytes shown in Table 1. Concentrations of detected analytes were compared to U.S. Environmental Protection Agency (USEPA) Maximum Contaminant Levels (MCLs) and Secondary Drinking Water Regulations (SDWRs) for drinking water. MCLs are legally enforceable water quality standards for public water supplies and SDWRs are non-enforceable standards where concentration exceedances may impact aesthetic components of water. Comparison of analytical results to USEPA MCLs and SDWRs revealed that only the manganese, pH, and turbidity concentrations exceeded or were outside the range of an MCL or SDWR. The manganese concentration (0.0600 mg/L) was slightly higher than the SDWR concentration of 0.05 mg/L and the pH value (5.62 standard units [SU]) was outside the SDWR range of 6.5–8.5 SU. The turbidity concentration of 1.14 nephelometric turbidity

units (NTU) slightly exceeded the post-filtration MCL value of 1 NTU, although it is likely that filtration would reduce the turbidity of water produced from the well. A summary of laboratory results is shown in Table 1.

**Table 1: Summary of Pavilion Well Sampling Results for Detected Analytes.**

Analyte Class	Analyte	Concentration (mg/L <sup>a</sup> )	USEPA <sup>b</sup> Drinking Water Standard (mg/L)
General Chemistry	Hardness	12.3	--- <sup>c</sup>
	Nitrate	1.68	10
Metals	Barium	0.0480	2
	Calcium	2.01	---
	Magnesium	1.78	---
	Manganese	0.0600	0.05
Volatile Organic Compounds	Volatile Organic Compounds (All Measured Compounds)	Below Laboratory Detection Limits	Dependent on Compound
Pesticides	Pesticides (All Measured Compounds)	Below Laboratory Detection Limits	Dependent on Compound
Field-Measured Parameter	pH	5.62 S.U.	6.5 – 8.5
	Specific Conductivity	60 µS/cm	---
	Temperature	20.9°C	---
	Turbidity	1.14 NTU	1 (post-filtration standard)

<sup>a</sup>mg/L = milligrams per liter

<sup>b</sup>USEPA = U.S. Environmental Protection Agency

<sup>c</sup>--- = drinking water standard does not exist for this compound

Blue text indicates a primary Maximum Contaminant Level and orange text indicates a Secondary Drinking Water Regulation.

Overall, sampling results indicate that the quality of groundwater from the Pavilion Well is generally good. It is reasonable to assume that groundwater quality produced from the Red Barn Well and Well B would generally be of similar quality, although a certain amount of variation should be expected. Water quality samples will be collected from the Red Barn Well and Well B during the VDH-required 48-hour constant rate pumping tests for public wells, which will provide additional information about groundwater quality within the subject site's bedrock aquifer.

#### **4.0 WELL INSTALLATION, MODIFICATION, AND TESTING ACTIVITIES**

ECS installed two test wells (Well A and Well B) and modified the construction of the existing Red Barn Well as part of previously completed groundwater exploration activities at the site. The planned development will use the Red Barn Well and Well B to supply the entire potable demand of the subject site. Well A will not be used as a supply well due to its low yield. A description of well installation/modification and testing activities performed in relation to these wells is provided in the following subsections of this report.

#### 4.1 Red Barn Well

The Red Barn Well will be used as a supply well for the planned development and is located approximately 53 feet from the existing Red Barn structure at the location shown in Figures 2 and 3. ECS completed characterization activities of the well to evaluate its construction and yield. Characterization activities included completion of a down-well camera survey and a 6-hour step-drawdown pumping test. Following the completion of characterization activities, the well's construction was modified to meet VDH-ODW Class II public well construction requirements. A description of Red Barn Well characterization and construction modification activities is provided below, and a Water Well Completion Report and geologic log is included within Appendix A.

##### 4.1.1 Red Barn Well Characterization

ECS completed a camera survey and 6-hour duration step-drawdown pumping test of the Red Barn Well prior to modifying its construction. The purpose of the camera survey was to determine the well's construction and the purpose of the step-drawdown pumping test was to evaluate the well's yield.

The Red Barn Well camera survey showed that 6-inch diameter PVC casing was present from above ground surface to a depth of 53 feet bgs and that the well was installed to a total depth of 108 feet bgs. Grout was not visible at the base of the casing and no perforations or damage to the casing was observed. Several shallow fracture zones were observed within the open-borehole portion of the well, with the most prominent fractures being present at depths of 58.0–58.7 feet bgs, 65.2–66.6 feet bgs, 72.2 feet bgs, and 85.8 feet bgs.

A six-hour duration step-drawdown pumping test of the Red Barn Well was completed to evaluate the well's pumping yield. The step-drawdown test consisted of completing three successive pumping steps, with each step lasting for a duration of two hours. The target pumping rates for each of the steps were 15 gpm, 21 gpm, and 27.5 gpm. Based on testing findings and the assumption that the well's water level during pumping should remain at or above the base of the well's casing due to the presence of shallow water-bearing fractures, it was determined that the Red Barn Well appeared capable of sustainably pumping at a rate of up to 30 gpm, although daily periods of rest would be recommended. This maximum pumping rate was based on limited-duration pumping test data, and as such, it was noted that actual groundwater levels within the well during pumping could deviate from projected levels due to influences from hydrogeologic boundary conditions arising at times beyond the testing duration. Longer duration constant-rate pumping testing required by VDH-ODW and Albemarle County as part of the well approval process is expected to provide additional information that will be used to evaluate the Red Barn Well's maximum pumping capacity and will better evaluate potential hydrogeologic boundary influences. A summary of findings from the Red Barn Well step-drawdown pumping test is provided in Table 2 and data plots are provided within Appendix B.

**Table 2: Red Barn Well Step-Drawdown Test Findings (Pre- Modification).**

<b>Step &amp; Pumping Rate</b>	<b>Depth to Water at End of Step (feet bgs<sup>a</sup>)</b>	<b>Drawdown at End of Step (feet)</b>	<b>Specific Capacity (gpm/ft<sup>b</sup>)</b>
Step 1 (14.8 gpm <sup>c</sup> )	27.78	6.89	2.15
Step 2 (20.6 gpm)	32.67	11.78	1.75
Step 3 (27.3 gpm)	37.69	16.80	1.63

<sup>a</sup>bgs = below ground surface.

<sup>b</sup>gpm/ft = gallons per minute per foot of drawdown.

<sup>c</sup>gpm = gallons per minute.

ECS discussed the Red Barn Well's construction with VDH-ODW and was informed that the well did not meet public well construction standards due to the apparent lack of a neat cement grout annular seal and the insufficient wall thickness of the casing. As such, it was determined that the well's construction must be modified to meet Class II public well construction requirements to allow the well to be used as a potable source of water for the planned development.

#### 4.1.2 Red Barn Well Construction Modification

ECS's Principal Hydrogeologist, Mr. Thomas Nelson, met onsite with Mr. James Simmons, Mr. Ken DiGuilio, and Ms. Karen Austin with the VDH-ODW on April 11, 2023. VDH-ODW staff visually observed the Red Barn Well's location and were informed of the plan to modify the well's construction to meet Class II public well standards by Mr. Nelson during this meeting. Email correspondence with Mr. Steven Kvech, Deputy Field Director for the VDH-ODW's Lexington Office, was later exchanged where Mr. Kvech stated that the construction modifications described herein would be acceptable for the well to meet Class II public well standards.

Red Barn Well modification activities began on April 24, 2023. Well modification was performed by Royall Pump and Well Company of Powhatan, Virginia. ECS personnel were onsite during drilling activities to compile a geologic log of the well, to record the depths of water-bearing zones, and to document the well's construction. A geologic and construction log of the modified Red Barn Well is included within Appendix A.

An attempt was made to pull the well's existing casing, although this was unsuccessful due to the well having been completed with several relatively short sections of casing that were connected with unglued slip fittings. As such, the casing immediately pulled apart when an upward force was applied. The remaining casing was removed using a reaming drill bit and it was observed during reaming that grout did not appear to be present between the casing and the borehole wall. The surface borehole was reamed to a depth of 56 feet bgs, during which time the entirety of the former PVC casing was removed. New heavy-wall (0.280-inch wall thickness), 6-inch inner diameter galvanized steel casing with a drive shoe was then placed within the surface boring to a depth of 56 feet bgs and was grouted using neat cement from the base of the casing to ground surface using tremie grout methods. Sediment and debris that had fallen into the original production boring was then

removed by reaming to the well's original depth of 108 feet bgs and to a diameter of six inches. An air-lift yield measurement of 34 gpm was recorded at a depth of 108 feet bgs.

Following reaming to 108 feet bgs, the Red Barn Well was then deepened to 600 feet bgs with a 6-inch diameter borehole in an effort to increase the well's yield. The general bedrock lithology that was observed during well deepening consisted of dark gray/blue metagraywacke with variable amounts of quartz and feldspar. Only 1 gpm air-lift yield was added during well deepening. As such, the shallow water-bearing fractures noted during the camera survey that were present from approximately 58–86 feet bgs appear to be the only significant water-bearing fractures supplying water to the Red Barn Well. The well's final air-lift yield at its total depth was 35 gpm and it is likely that its maximum pumping yield is similar to that determined during prior step-drawdown testing (i.e., approximately 30 gpm) before the well's construction was modified. A waterproof well cap was affixed to the casing's stickup following the completion of well drilling and the section of concrete pipe that had been present at ground surface over the casing stickup was placed back over the wellhead.

#### 4.2 Well A

Well A will not be used as a supply well for the planned development due to its low yield. Well A is located within a grazing field approximately 440 feet from the nearest site boundary (Figures 2 and 3). VDH-ODW conducted a site visit on December 21, 2022 to observe the location of Well A and provided approval of the well location via a letter dated January 11, 2023, which is included as Appendix C. The VDH-ODW letter classified the well as a Class II public supply well. Although Well A will not be used as a supply well, it will be used as an observation well during VDH-required 48-hour constant-rate aquifer testing. A description of Well A installation activities is provided below, and a Water Well Completion Report and geologic log is included within Appendix A.

##### 4.2.1 Well A Installation

Well A was completed on February 14, 2023 to a depth of 500 feet bgs but was later deepened to 900 feet bgs in an attempt to increase the well's yield. A 10-inch diameter boring was drilled to a depth of 96 feet bgs and 6-inch diameter steel casing was set to a depth of 96 feet bgs. Cement grout was installed in the annular space from 0–96 feet bgs using tremie grout methods. A waterproof well cap was affixed to the casing's stickup. The general lithology consisted of approximately 45 feet of overburden comprised primarily of an orange/brown clayey silt with a zone of weathered rock from 35–45 feet bgs. Bedrock was encountered at 45 feet bgs and generally consisted of a dark gray/blue metagraywacke with some quartzite. Various fractured zones were encountered at 167–171 feet bgs, 176–198 feet bgs, and 440–500 feet bgs. A water-bearing zone at 440–458 feet bgs was identified and yielded approximately 2 gpm. Upon completion of the well to a depth of 500 feet bgs, an air-lift test was conducted and resulted in a measured yield of 2 gpm. Fracturing was also encountered at 500–560 feet bgs during well deepening, which increased the well's air-lift yield to 4 gpm. The well's final air-lift yield at 900 feet bgs was observed to be 4 gpm. Based on the well's low yield, it was not selected for aquifer testing.

#### 4.3 Well B

Well B will be used as a supply well for the planned development and is located within a grazing field approximately 520 feet from the nearest site boundary (Figures 2 and 3). VDH-ODW conducted a site visit on December 21, 2022 to observe the location of Well B

and provided approval of the well location via a letter dated January 11, 2023, which is included as Appendix C. The VDH-ODW letter classified the well as a Class II public supply well. A description of Well B installation and step-drawdown testing activities is provided below, and a Water Well Completion Report and geologic log is included within Appendix A.

#### 4.3.1 Well B Installation

Well B was completed as a 6-inch diameter well to a depth of 600 feet bgs on March 10, 2023. A 10-inch diameter surface borehole was drilled to a depth of 59 feet bgs and 6-inch diameter heavy-wall steel casing with a 0.28-inch wall thickness was set to a depth of 59 feet bgs. Cement grout was installed in the annular space between the borehole wall and the casing from 0–59 feet bgs using tremie grout methods. A waterproof well cap was affixed to the casing's stickup following the completion of well drilling. The general lithology consisted of approximately 38 feet of overburden comprised primarily of a tan silt with some gravel. Bedrock was encountered at 38 feet bgs and generally consisted of a dark gray/blue metagraywacke with some quartzite. Two primary water-bearing zones were identified during drilling. The first zone was present from approximately 70–220 feet bgs, where the air-lift yield gradually increased to 18 gpm while drilling this depth interval. A second water-bearing zone was identified from 300–360 feet bgs, where the air-lift yield gradually increased from 18 gpm to 32 gpm. Upon completion of the well to a depth of 600 feet bgs, an air-lift test was conducted and resulted in a measured yield of 32 gpm.

#### 4.3.2 Well B Step-Drawdown Testing

ECS completed a nearly 6-hour duration step-drawdown pumping test of Well B on May 12, 2023, to estimate the well's maximum pumping yield. Groundwater levels were measured in the pumping well during testing using a vented pressure transducer capable of measuring groundwater levels to the nearest 1/1,000<sup>th</sup> of a foot. The pressure transducer was installed within a sounding tube to reduce water level disturbance and wire entanglement. Additionally, groundwater levels were periodically measured using an electronic water level meter capable of measuring groundwater levels to the nearest 1/100<sup>th</sup> of a foot. A 3-inch diameter, 10-horsepower submersible pump capable of pumping at a maximum rate of up to 80 gpm was used during testing and was installed to a depth of 300 feet bgs. The sounding tube was installed to a depth of approximately 260 feet bgs. The pump was powered using a trailer-mounted diesel generator. The manifold at the wellhead contained a gate valve to adjust the flow rate, a totalizer meter capable of providing instantaneous flow rate readings and total pumped volume, and a sampling spigot. Approximately 200 feet of discharge piping was used to divert pumped water in a southern direction for discharge at the land surface at a distance of approximately 100 feet from a pond.

The step-drawdown test consisted of three successive pumping steps. The first two steps lasted for a duration of two hours each, but it was necessary to terminate the third step 20 minutes short of the two-hour mark due to excessive drawdown within the well. The target pumping rates for each of the steps were 20 gpm (Step 1), 35 gpm (Step 2), and 40 gpm (Step 3). A pumping rate of approximately 60 gpm was initially used for the third step, but within 10 minutes of starting the step it became apparent that the rate of drawdown had significantly increased and that such a high rate would be unsustainable. The pumping rate was then reduced to 40 gpm for the remainder of the step to reduce the rate of drawdown. Based on totalizer readings recorded at the beginning and end of each step, the actual average pumping rates used during each of the steps were 20.1 gpm, 34.7 gpm,

and 39.9 gpm. The static groundwater level prior to the start of the pumping test was 12.76 feet below the well's top of casing (btoc) (i.e., approximately 9 feet bgs). Graphs showing data collected during the step-drawdown pumping test are included within Appendix B and a table showing the depth to water, drawdown, and specific capacity at the conclusion of each step is included as Table 3.

**Table 3: Well B Step-Drawdown Test Findings.**

<b>Step &amp; Pumping Rate</b>	<b>Depth to Water at End of Step (feet btoc<sup>a</sup>)</b>	<b>Drawdown at End of Step (feet)</b>	<b>Specific Capacity (gpm/ft<sup>b</sup>)</b>
Step 1 (20.1 gpm <sup>c</sup> )	33.09	20.33	0.989
Step 2 (34.7 gpm)	58.22	45.46	0.763
Step 3 (39.9 gpm)	>240	>227.24	<0.176

<sup>a</sup>btoc = below top of casing.

<sup>b</sup>gpm/ft = gallons per minute per foot of drawdown.

<sup>c</sup>gpm = gallons per minute.

ECS used data collected during the step-drawdown pumping test to estimate the well's maximum pumping yield. The well's maximum pumping yield was evaluated using the pumping test data in conjunction with extrapolated specific capacity values and the application of the Jacob (1946) equation and Bierschenk (1964) well loss calculations. The rapid increase in the rate of drawdown that occurred following the dewatering of the well's shallow water-bearing fractures was also considered. Based on the findings of this analysis and the assumption that the well's water level during pumping should remain at or above the shallowest water-bearing fracture observed during drilling (i.e., 70 feet bgs), Well B appears capable of sustainably pumping at a rate of up to 32 gpm, although periods of rest would be recommended to allow for water level recovery.

It is important to note that this maximum pumping rate is based on limited-duration pumping test data. As such, it is possible that actual groundwater levels within the well at the evaluated pumping rates could deviate from projected groundwater levels due to influences from hydrogeologic boundary conditions arising at times beyond the testing duration. The longer duration constant-rate pumping test required by VDH-ODW and Albemarle County as part of the well approval process is expected to provide additional information that will be used to evaluate Well B's maximum pumping capacity.

## **5.0 WELL INVENTORY**

### **5.1 Evaluation of Proximal Well Users**

Municipal water service utilities are unavailable at and in the vicinity of the subject site. As such, developed properties in the vicinity of the site rely on private domestic wells for their water supply. ECS evaluated parcels located within 1,000 feet of the subject site to identify which properties are likely to use a domestic well. The evaluation was completed within a geospatial database using publicly available land parcel, structure location, and

address point shapefile data provided by Albemarle County and Fluvanna County. Parcels developed with one or more structures and parcels that were assigned addresses were considered to be properties that are likely to contain a domestic supply well.

A total of 66 properties located within 1,000 feet of the subject site were identified as likely to contain a domestic supply well. Well locations were assumed to correspond to the locations of the primary structure at each property, which is a reasonable assumption given that the majority of domestic wells are installed in proximity to primary residential buildings. Of the 66 properties containing wells, the well locations at nine of these properties appear likely to be located within 1,000 feet of one of the subject site's two supply wells (i.e., the Red Barn Well or Well B) and the well locations at the remaining properties appear to be located more than 1,000 feet, and as far as 7,450 feet, from the subject site's supply wells. The nearest offsite well is located at 6089 Rolling Road South, which is estimated to be 350 feet from the Red Barn Well. ECS attempted to identify the exact location of this well while standing at the property line but was unable to visually observe its location within approximately 100 feet of the subject site boundary. As such, the well appears likely to be located at the northern portion of the property that was not visible from the property line. The nearest offsite well to Well B is estimated to be located approximately 1,830 feet to the northwest. A map showing the locations of properties within 1,000 feet of the subject site that are likely to use a private domestic well are shown in Figure 7 and a table showing the addresses and estimated distances of each property's well from the nearest subject site supply well is included as Appendix D.

## 5.2 Proximal Well Record Search

ECS submitted Freedom of Information Act (FOIA) requests to the Blue Ridge Health Department for well records at properties located within a 2,500-foot radius of Wells A and B, which included properties in close proximity to the Red Barn Well. The FOIA documents contained well records for eight offsite properties. Seven out of the eight wells were located along Rolling Road South while the eighth well was located at 1421 Little Wyoming Lane, which is to the north of the subject site. Well record information showed that each of the wells except for the well located at 7022 Rolling Road South is a bedrock well. The well at 7022 Rolling Road South is a shallow bored well that was installed to a depth of 60 feet bgs. While shallow bored wells are more susceptible to water production issues than drilled bedrock wells, the nearest supply well at the subject site (Well B) is located approximately 2,190 feet from the well and would not be expected to adversely impact the bored well. The average well depth, yield, and depth to bedrock at the seven drilled wells was 173 feet, 9 gpm, and 53 feet, respectively. The locations of the offsite properties where well record information was available is shown in Figure 8 and the well records are included as Appendix E.

## **6.0 GROUNDWATER MANAGEMENT PLAN & CONTINGENCY PLAN**

### 6.1 Groundwater Management Plan

Construction and development will not occur within each supply well's Class II WHPA, other than construction related to a well building, water distribution system, and treatment system. Temporary posts, fencing, or other restrictive barriers will be placed around the 50-foot zone surrounding each well (i.e., the Class II WHPA) to ensure that construction equipment does not intrude upon the WHPA during site development. During construction of well-related features (i.e., well building, water distribution system, etc.), chemicals, if



used, will be stored at least 50 feet from the wellhead. The neat cement grout annular surface seal would provide protection against surface contaminants during and after construction. Following the conclusion of site development activities, the Class II WHPAs will be maintained by restricting the storage or application of chemicals within the WHPAs.

## 6.2 Contingency Plan

The site owner will contact a Virginia-licensed well drilling firm to evaluate the water system if a supply well(s) ceases to produce water. The evaluation will consist of assessing the pump and well equipment to determine whether it appears to be functioning properly. If a problem is diagnosed during the inspection that is not related to a lowering of the groundwater level, but is deemed to be due to normal wear and usage, repairs will be made to the system to fix the defective component. If the cause of groundwater supply interruption is not clear, a hydrogeologic consultant (Virginia-Certified Professional Geologist) will be retained to evaluate the well and to conduct site-specific investigation deemed appropriate to identify the cause of the decline in groundwater levels. Such investigation may include installation of in-situ data loggers to monitor water levels within the impacted well. Similarly, if a supply well is found to be contaminated, distribution of the impacted water will immediately be ceased and a hydrogeologic consultant (Virginia-Certified Professional Geologist) will be retained to report the contamination to applicable regulatory agencies and to determine the source and extent of contamination.

In the event that a supply well is deemed to no longer be operational due to impacts caused by a critical lowering of groundwater levels or by contamination, the site owner shall install an additional well(s) to replace the lost water supply. Two additional well drilling targets have been identified by ECS using fracture trace analysis and electrical resistivity surface geophysical methods, and both well targets have already received approval by the VDH-ODW for the installation of Class II public supply wells. The planned development will not encroach within 50 feet of either well target (i.e., Class II WHPA) to allow for a well to be constructed at the target locations in the event that this becomes necessary due to water supply or quality issues. Potable water will be provided to the planned development from an external provider, or the development will be temporarily closed, until a new water supply source is established.

## **7.0 CLOSING**

ECS is pleased to provide this Draft GWMP documenting hydrogeologic conditions and existing supply wells that are planned for use at the Briery Creek Farm Site. The Briery Creek Farm site is located at 6055 Rolling Road South in Scottsville, Virginia. The GWMP is being submitted to satisfy requirements outlined within Article X of the Albemarle County Code and has been written in accordance with Section 2 of the Albemarle County Design Standards Manual for Engineering.

The site's proposed development will include approximately 250 vacation rental cabins and various other amenities that will be serviced by a central water system that will be supplied by groundwater supply wells. Two Class II public supply wells, which are referred to as the Red Barn Well and Well B, will provide water to the planned development. Preliminary information obtained during well installation and step-drawdown testing indicates that the wells appear capable of meeting the site's expected water demand. Groundwater quality at the site appears to be acceptable for potable use and no significant

contaminant threats were identified that appear likely to impact either well. The nearest offsite well appears to be located at least 350 feet from the closest subject site supply well and the majority of wells in the vicinity of the site appear to be bedrock wells, which are less susceptible than shallow bored wells to impacts caused by drought conditions or surficial contaminant sources. Information obtained during 48-hour constant rate aquifer testing and water quality sampling will provide additional information regarding the capacity and quality of the site's supply wells.

## **8.0 REFERENCES**


Evans, N.H. 1994. Geology of the Simeon quadrangle, Virginia, scale 1:24,000. Virginia Division of Mineral Resources Publication 134

Virginia Division of Mineral Resources 2003. Expanded explanation: geologic map of Virginia, scale 1:500,000. Publication 147, 85 pp.

## **9.0 LIMITATIONS**

The work performed in conjunction with this project, and the data developed, are intended as a description of available information at the study area. Generally accepted industry standards were used in the preparation of this report. Results from future testing may vary significantly as a result of natural conditions, a changing environment, or the limits of analytical capabilities. This report does not warrant against future operations or conditions, nor does it warrant against operations or conditions present of a type or at a specific location not evaluated.

## Figures




**Figure 1: Site Location Map**


Briery Creek Farm Site  
 Albemarle & Fluvanna County, Virginia

**Legend**

 Subject Site



1. Main Entry
2. Entry Drive
3. Arts & Crafts House
4. Guest Check-in
5. Dining Facility & Camp Store
6. Pool Building
7. Fitness
8. Health & Wellness
9. Guests Meeting Space
10. Walking Paths
11. Lakes
12. Open Meadow
13. Pastures
14. Horse Barn
15. Existing Barn/Maintenance Facility
16. Emergency Access Only
17. Exit Drive



**Figure 2: Site Concept Plan and Supply Well Locations**

Briery Creek Farm Site  
 Albemarle & Fluvanna County, Virginia


**Legend**

- Subject Site
- Planned Supply Well



0 500 1,000 2,000  
 Feet





**Figure 3: Site Layout Map**

Briery Creek Farm Site  
 Albemarle & Fluvanna County, Virginia


**Legend**

- Subject Site
- County Boundary Line (approximate)
- Road

**Existing Well**

- Used as Supply Well by Current Development
- ⊕ Installed by ECS during Groundwater Exploration Effort





**Figure 4: Topographic and Hydrologic Mapping**

**Legend**

- Subject Site
- Stream
- Reservoir
- Topographic Contour (C.I. = 10 ft)**
- Index Contour
- Intermediate Contour
- Ground Elevation**
- High : 570.01 ft amsl
- Low : 359.08 ft amsl

Briery Creek Farm Site  
Albemarle & Fluvanna County, Virginia



0 600 1,200 2,400  
Feet

*Map Note:*  
Topographic mapping is provided  
by the National Elevation Dataset  
(1-meter Lidar) and hydrologic  
mapping is provided by the  
National Hydrography Dataset.



ECS Project No. 47-16310-C




**Legend**

- Subject Site
- Fault

**ORIG\_LABEL**

- [Zpm = metagraywacke, quartzose schist, and melange
- [ca = Candler Formation (phyllite and schist)
- my = mylonite, mylonite gneiss, and cataclastic rocks



**Figure 5: Geologic Mapping**

Briery Creek Farm Site  
Albemarle & Fluvanna County, Virginia




*Map Note:*  
Geologic mapping by the Virginia  
Division of Mineral Resources (2003)



ECS Project No. 47-16310-C








**Figure 6: Estimated Groundwater Recharge and Discharge Zones**


Briery Creek Farm Site  
Albemarle & Fluvanna County, Virginia

**Legend**

-  Subject Site
-  Estimated Groundwater Discharge Area (81.4 acres)
-  Estimated Groundwater Recharge Area (642.4 acres)

0 600 1,200 2,400  
Feet






**Figure 7: Well Locations on Parcels within 1,000 Feet of Subject Site Boundary**

Briery Creek Farm Site  
 Albemarle & Fluvanna County, Virginia


**Legend**

- Subject Site
- Planned Supply Well
- Well Locations (estimated)**
- Well (Albemarle County Property)
- Well (Fluvanna County Property)
- Well (Albemarle & Fluvanna Counties Property)



*Map Note:*  
 Well locations are estimated based on primary structure locations.





**Figure 8: Proximal Properties with Available Well Records**

Briery Creek Farm Site  
 Albemarle & Fluvanna County, Virginia

**Legend**

- Subject Site
- Planned Supply Well
- Offsite Well with Available Record Information



## **Appendix A**

### **Water Well Completion Reports & Geologic Well Logs**

## **Red Barn Well Completion Report & Geologic Log**

Virginia Water Well Completion Report

<b>Topographical Data</b> Datum _____ Latitude 037°86'61.2" N Longitude 078°42'47.6" W Topo Map _____ Elevation _____ ft Formation _____ Lithology _____ River Basin _____ Province Piedmont Type Logs _____ Cuttings _____ Water Analysis _____ Aquifer Test _____ Well Notes _____ Treatment Eqp _____	<b>General Contractor</b> Name Tom Nelson - ECS Mid-Atlantic Address 4004 Hunterstand Ct. Suite 102 City Charlottesville State VA Zip 22911- Phone _____ Well Designation or No. Red Barn Well <b>Drilling Contractor</b> Name Royall Pump & Well Company, Inc. Address 2958 Anderson Highway City Powhatan State VA Zip 23139- Phone (804) 598-8147 Fax (804) 598-1291 Email info@royallpumpandwell.com License 014253	<b>Permit Data</b> DEQ Permit _____ VDH WELL # _____ Building Permit _____ PWSID _____ <b>Well Address</b> Tax Map I.D. _____ Subdivision _____ Section _____ Block _____ Lot Number _____ Well Owner Reverton Farms Well Address 6055 Rolling Rd. Well City Scottsville State VA Zip 24590- Well Classes Class IIB
-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

Well Location (feet/miles) \_\_\_\_\_ (direction) \_\_\_\_\_ of \_\_\_\_\_  
If possible submit map with well location marked.  
Well Location (feet/miles) \_\_\_\_\_ (direction) \_\_\_\_\_ of \_\_\_\_\_  
Drill Dates Date Started 4/25/2023 Date Completed 4/30/2023 Type Rig Air Rotary

**WELL DATA**  
 New  Reworked  Deepened  Abandoned  
Total Depth: 603 ft. Depth to Bedrock: 45 ft.

**Hole Size (Also include reamed zones)**  
(1) 11 inches from 0-45 to \_\_\_\_\_ ft.  
(2) 10 inches from 45 to 55 ft.  
(3) 6 inches from 55 to 603 ft.

**Casing Size (I.D.) and Material**  
(1) 6.00 inches from 0 to 55 ft.  
Material: Galvanized Steel TC  
Weight per ft 18.97 or wall thickness .280 in.  
(2) \_\_\_\_\_ inches from \_\_\_\_\_ to \_\_\_\_\_ ft.  
Material: \_\_\_\_\_  
Weight per ft \_\_\_\_\_ or wall thickness \_\_\_\_\_ in.  
(3) \_\_\_\_\_ inches from \_\_\_\_\_ to \_\_\_\_\_ ft.  
Material: \_\_\_\_\_  
Weight per ft \_\_\_\_\_ or wall thickness \_\_\_\_\_ in.

**Screen Size and Slot for Each Zone**  
(1) \_\_\_\_\_ inches from \_\_\_\_\_ to \_\_\_\_\_ ft.  
Slot Size: \_\_\_\_\_ Type: \_\_\_\_\_  
Material: \_\_\_\_\_  
(2) \_\_\_\_\_ inches from \_\_\_\_\_ to \_\_\_\_\_ ft.  
Slot Size: \_\_\_\_\_ Type: \_\_\_\_\_  
Material: \_\_\_\_\_  
(3) \_\_\_\_\_ inches from \_\_\_\_\_ to \_\_\_\_\_ ft.  
Slot Size: \_\_\_\_\_ Type: \_\_\_\_\_  
Material: \_\_\_\_\_  
(4) \_\_\_\_\_ inches from \_\_\_\_\_ to \_\_\_\_\_ ft.  
Slot Size: \_\_\_\_\_ Type: \_\_\_\_\_  
Material: \_\_\_\_\_

**Gravel Pack**  
Size \_\_\_\_\_ From \_\_\_\_\_ to \_\_\_\_\_ ft.  
Size \_\_\_\_\_ From \_\_\_\_\_ to \_\_\_\_\_ ft.

**Grout**  
From -1 to 55 ft. Type: Cement/Neat  
From \_\_\_\_\_ to \_\_\_\_\_ ft. Type: \_\_\_\_\_

**Lower Casing Seal**  
 K-Packer  Drive Sho  Well Packer  Shale Trap  
6 x 7.5 inches from 55 to 56 ft.

**WATER DATA**  Artesian Flow Rate: \_\_\_\_\_ gpm  
Static Water Level: 23 PH: \_\_\_\_\_  
Established Well Yield: 40 gpm Water Temp: \_\_\_\_\_ F  
Stabilized Pumping Level \_\_\_\_\_  
Stabilized Pumping Yield \_\_\_\_\_ gpm afte \_\_\_\_\_ hours  
Comment on water quality \_\_\_\_\_

**WATER ZONES**  
(1) 27.5 gpm From 57 to 58  
(2) 12.4 gpm From 425 to 427 (3) \_\_\_\_\_ gpm From \_\_\_\_\_ to \_\_\_\_\_  
(4) \_\_\_\_\_ gpm From \_\_\_\_\_ to \_\_\_\_\_ (5) \_\_\_\_\_ gpm From \_\_\_\_\_ to \_\_\_\_\_

**USE DATA**  
Type of Use:  Drinking  Livestock Watering  Irrigation  
 Food Processing  Household  Manufacturing  
 Fire Safety  Cleaning  Recreation  
 Aestheti  Cooling/Heating  Injection  
Other: \_\_\_\_\_  
Type of Facility:  Domestic  Public Water Supply  Public Institution  
 Farm  Industry  Commercial  
Other: \_\_\_\_\_

**PUMP DATA**  
Type: Submersible 3 inch Series 22 gpm  
HP 1.5 Capacity 22 gpm at 200 ft. head  
Intake Dept 80 ft Voltage 230  
Riser Pipe Size 1 Type Polyethylene Coil WireSize 10  
Model Number \_\_\_\_\_

**WELLHEAD** Type of Well Seal/Cap: Vermin Proof Ventilated  
Pressure Tank \_\_\_\_\_ Location: \_\_\_\_\_  
Sample Tap: \_\_\_\_\_ Measurement Port: \_\_\_\_\_  
Well Vent: \_\_\_\_\_ Pressure Relief Valve: \_\_\_\_\_  
Gate Valve: \_\_\_\_\_ Check Valve (if required): \_\_\_\_\_  
Electrical Disconnect Switch on Power Supply: \_\_\_\_\_

**DISINFECTION** Disinfected \_\_\_\_\_ Date: \_\_\_\_\_  
Disinfection Us \_\_\_\_\_ Amount: \_\_\_\_\_ Hours: \_\_\_\_\_

**ABANDONMENT**  
Date \_\_\_\_\_ Casing Pulled  Yes  No  N/A  
Well Disinfected \_\_\_\_\_ Type: \_\_\_\_\_ Amount: \_\_\_\_\_  
(1) Grout/Backfill From \_\_\_\_\_ to \_\_\_\_\_ ft. Material: \_\_\_\_\_  
(2) Grout/Backfill From \_\_\_\_\_ to \_\_\_\_\_ ft. Material: \_\_\_\_\_  
(3) Grout/Backfill From \_\_\_\_\_ to \_\_\_\_\_ ft. Material: \_\_\_\_\_

Virginia Water Well Completion Report (continued)

Well Owner: Tom Nelson - ECS Mid-Atlantic 4004 Hunterstand Ct. Suite 102 Charlottesville VA 22911-	Permits: DEQ Permit _____ DOH Well # _____ Building Permit _____ PWSID _____
Well Address: 6055 Rolling Rd. Scottsville VA 24590-	Well Location: Latitude 037°86'61.2'' N Longitude 078°42'47.6'' W

<b>Well Lot Dedicated</b> Size: _____ ft by: _____ ft Well House _____ Distance to nearest pollutant source _____ ft Type _____ Distance to nearest property line _____ ft Waste Disposa _____ Distance to Building _____ ft	<b>Type of Well Construction</b> <input type="radio"/> Bored Well <input checked="" type="radio"/> Consolidated Well <input type="radio"/> Unconsolidated Well <input type="radio"/> Multiple Screen Unconsolidated Well <input type="radio"/> Abandoned Bored Well <input type="radio"/> Abandoned Consolidated Well <input type="radio"/> Abandoned Unconsolidated Well
------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

**Water Service Pipe**

Checked under \_\_\_\_\_ p.s.i. for \_\_\_\_\_ minutes


Material \_\_\_\_\_ Pipe Size \_\_\_\_\_ in.

Installer \_\_\_\_\_ Installed Dat \_\_\_\_\_

**Driller's Log**

Depth (feet)		Type of Rock or Soil	Remarks
From:	To:		
0	1	Top Soil	
1	18	Red Clay	18
18	32	Brown Sandstone	
32	41	Light Brown/Red Sandstone	
41	44	Pinl/Red Weathered Rock	
44	51	Red/Grey Soft Weathered Rock	
51	603	Grey Rock	
		Mr. Garnett B. Williams of ECS	
		Performed Formation Log	

I certify that the information contained herein is true and correct and that this well and/or system has been installed and constructed in accordance with the requirements for well construction as specified in compliance with appropriate county or independent city ordinances and the laws and rules of the state where the well was installed.

Signature:  \_\_\_\_\_

Robert W. Royall Date: 5/6/2023 License Number 014253

Seal

**Project:** 47-16310-B

**Well:** Red Barn Well

**Name:** Reventon Farms Site

**Well Depth:** 600 ft bgs

**Location:** Albemarle County, VA

**Well Diameter:** 6-inch

**Logger:** Garnett Williams, P.G.

**Well Coordinates:** 37.866101° N, -78.424784° W



**Manager:** Thomas Nelson, P.G.

**TOC Elevation:** 508 ft amsl (approximate)

**Casing Depth:** 56 ft bgs

**Drilling Firm:** Royall Pump & Well

**Completion Date:** 4/25/2023

**Airlift Yield:** 35 gpm


**Drilling Method:** Air Rotary

**Approximate Static Water Level:** Not measured

**Water Bearing Zones:** 56-108 ft bgs (34 gpm)

**Notes:** Construction described herein represents a well modification. Former well depth was 108 ft bgs.

Depth (feet)	Lithology	Lithologic Description	Well Diagram
-----------------	-----------	------------------------	--------------





## **Well A Completion Report & Geologic Log**

<b>Topographical Data</b> Datum _____ Latitude 378°72'54.0'' N Longitude 078°42'48.3'' W Topo Map _____ Elevation 412 ft Formation _____ Lithology _____ River Basin _____ Province Piedmont Type Logs _____ Cuttings _____ Water Analysis _____ Aquifer Test _____ Well Notes _____ Treatment Eqp _____	<b>General Contractor</b> Name ECS Mid Atlantic LLC/ Thomas Nelson Address 4004 Hunterstand Court, #102 City Charlottesville State VA Zip 22911- Phone _____ Well Designation or No. WL001 <b>Drilling Contractor</b> Name Royall Pump & Well Company, Inc. Address 2958 Anderson Highway City Powhatan State VA Zip 23139- Phone (804) 598-8147 Fax (804) 598-1291 Email info@royallpumpandwell.com License 014253	<b>Permit Data</b> DEQ Permit _____ VDH WELL # _____ Building Permit _____ PWSID Proposed WL001 <b>Well Address</b> Tax Map I.D. _____ Subdivision _____ Section _____ Block _____ Lot Number _____ Well Owner _____ Well Address 6055 Rolling Road Well City Scottsville State Va Zip 24590- Well Classes Class IIB
Well Location (feet/miles) _____ (direction) _____ of _____ Location / Well Location (feet/miles) _____ (direction) _____ of _____ Drill Dates Date Started 2/10/2023 Date Completed 2/15/2023 Type Rig Air Rotary		If possible submit map with well location marked.
<b>WELL DATA</b> <input checked="" type="checkbox"/> New <input type="checkbox"/> Reworked <input type="checkbox"/> Deepened <input type="checkbox"/> Abandoned Total Depth: 900 ft. Depth to Bedrock: 40 ft.	<b>WATER DATA</b> <input type="checkbox"/> Artesian Flow Rate: _____ gpm Static Water Level: 32 PH: _____ Established Well Yield: 2 gpm Water Temp: _____ F Stabilized Pumping Level _____ Stabilized Pumping Yield _____ gpm after _____ hours Comment on water quality _____	<b>WATER ZONES</b> (1) 1 gpm From 430 to _____ (2) 1 gpm From 480 to _____ (3) 2 gpm From 700 to 800 (4) _____ gpm From _____ to _____ (5) _____ gpm From _____ to _____
Hole Size (Also include reamed zones) (1) 10 inches from 0 to 96 ft. (2) 6 inches from 96 to 900 ft. (3) _____ inches from _____ to _____ ft.	<b>USE DATA</b> Type of Use: <input type="checkbox"/> Drinking <input type="checkbox"/> Livestock Watering <input type="checkbox"/> Irrigation <input type="checkbox"/> Food Processing <input type="checkbox"/> Household <input type="checkbox"/> Manufacturing <input type="checkbox"/> Fire Safety <input type="checkbox"/> Cleaning <input type="checkbox"/> Recreation <input type="checkbox"/> Aestheti <input type="checkbox"/> Cooling/Heating <input type="checkbox"/> Injection Other: _____ Type of Facility: <input type="checkbox"/> Domestic <input checked="" type="checkbox"/> Public Water Supply <input type="checkbox"/> Public Institution <input type="checkbox"/> Farm <input type="checkbox"/> Industry <input type="checkbox"/> Commercial Other _____	<b>WATER ZONES</b> (1) 1 gpm From 430 to _____ (2) 1 gpm From 480 to _____ (3) 2 gpm From 700 to 800 (4) _____ gpm From _____ to _____ (5) _____ gpm From _____ to _____
Casing Size (I.D.) and Material (1) 6 inches from +2 to 96 ft. Material: Galvanized Steel TC Weight per ft _____ or wall thickness .280 in. (2) _____ inches from _____ to _____ ft. Material: _____ Weight per ft _____ or wall thickness _____ in. (3) _____ inches from _____ to _____ ft. Material: _____ Weight per ft _____ or wall thickness _____ in.	<b>PUMP DATA</b> Type: _____ inch Series _____ gpm HP _____ Capacity _____ gpm at _____ ft. head Intake Dept _____ ft Voltage _____ Riser Pipe Size _____ Type _____ WireSize _____ Model Number _____	<b>WELLHEAD</b> Type of Well Seal/Cap: Vermin Proof Ventilated Pressure Tank _____ Location: _____ Sample Tap: _____ Measurement Port: _____ Well Vent: _____ Pressure Relief Valve: _____ Gate Valve: _____ Check Valve(if required): _____ Electrical Disconnect Switch on Power Supply: _____
Screen Size and Slot for Each Zone (1) _____ inches from _____ to _____ ft. Slot Size: _____ Type: _____ Material: _____ (2) _____ inches from _____ to _____ ft. Slot Size: _____ Type: _____ Material: _____ (3) _____ inches from _____ to _____ ft. Slot Size: _____ Type: _____ Material: _____ (4) _____ inches from _____ to _____ ft. Slot Size: _____ Type: _____ Material: _____	<b>DISINFECTION</b> Disinfected _____ Date: _____ Disinfection Us _____ Amount: _____ Hours: _____	<b>ABANDONMENT</b> Date _____ Casing Pulled <input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A Well Disinfected _____ Type: _____ Amount: _____ (1) Grout/Backfill From _____ to _____ ft. Material: _____ (2) Grout/Backfill From _____ to _____ ft. Material: _____ (3) Grout/Backfill From _____ to _____ ft. Material: _____
Gravel Pack Size _____ From _____ to _____ ft. Size _____ From _____ to _____ ft.	<b>Grout</b> From 0 to 96 ft. Type: Pumped Cement From _____ to _____ ft. Type: _____	<b>Lower Casing Seal</b> <input type="radio"/> K-Packer <input checked="" type="radio"/> Drive Sho <input type="radio"/> Well Packer <input type="radio"/> Shale Trap 7.5 x 10 inches from 95 to 96 ft.



**Name:** Reventon Farms Site

**Well Depth:** 900 ft bgs



**Location:** Albemarle County, VA

**Well Diameter:** 6-inch

**Logger:** Dalton Carbaugh

**Well Coordinates:** 37.87254° N -78.424837° W (approximate)

**Manager:** Thomas Nelson, P.G.

**TOC Elevation:** 508 ft amsl (approximate)

**Casing Depth:** 96 ft bgs

**Drilling Firm:** Royall Pump & Well

**Completion Date:** 3/7/2023

**Airlift Yield:** 4 gpm


**Drilling Method:** Air Rotary

**Approximate Static Water Level:** Not measured

**Water Bearing Zones:** 440-458 ft bgs (2 gpm), 500-560 ft bgs (2 gpm)

**Notes:** Surface boring 10-inch diameter. 6-inch diameter casing set to 96 ft bgs. Cement grout installed in annular space from 0-96 ft bgs.

Depth (feet)	Lithology	Lithologic Description	Well Diagram
-----------------	-----------	------------------------	--------------



## **Well B Completion Report & Geologic Log**

<b>Topographical Data</b> Datum _____ Latitude 037°87'78.1'' N Longitude 078°42'62.9'' W Topo Map _____ Elevation 406 ft Formation _____ Lithology _____ River Basin _____ Province Piedmont Type Logs _____ Cuttings _____ Water Analysis _____ Aquifer Test _____ Well Notes _____ Treatment Eqp _____	<b>General Contractor</b> Name Thomas Nelson Address 4004 Hunterstand Court, #102 City Charlottesville, Va 22911 State VA Zip 22911- Phone _____ Well Designation or No. TW002 <b>Drilling Contractor</b> Name Royall Pump & Well Company, Inc. Address 2958 Anderson Highway City Powhatan State VA Zip 23139- Phone (804) 598-8147 Fax (804) 598-1291 Email info@royallpumpandwell.com License 014253	<b>Permit Data</b> DEQ Permit _____ VDH WELL # _____ Building Permit _____ PWSID Proposed <b>Well Address</b> Tax Map I.D. _____ Subdivision _____ Section _____ Block _____ Lot Number _____ Well Owner _____ Well Address 6055 Rolling Road Well City Scottsville State Va Zip 24590- Well Classes Class IIB
Well Location (feet/miles) _____ (direction) _____ of _____ Location / Well Location (feet/miles) _____ (direction) _____ of _____ Drill Dates Date Started 3/13/2023 Date Completed 3/17/2023 Type Rig Air Rotary If possible submit map with well location marked.		
<b>WELL DATA</b> <input checked="" type="checkbox"/> New <input type="checkbox"/> Reworked <input type="checkbox"/> Deepened <input type="checkbox"/> Abandoned Total Depth: 605 ft. Depth to Bedrock: 40 ft. Hole Size (Also include reamed zones) (1) 11 inches from 0 to 58 ft. (2) 6 inches from 58 to 605 ft. (3) _____ inches from _____ to _____ ft. Casing Size (I.D.) and Material (1) 6 inches from +2 to 58 ft. Material: Galvanized Steel TC Weight per ft _____ or wall thickness .280 in. (2) _____ inches from _____ to _____ ft. Material: _____ Weight per ft _____ or wall thickness _____ in. (3) _____ inches from _____ to _____ ft. Material: _____ Weight per ft _____ or wall thickness _____ in.	<b>WATER DATA</b> <input type="checkbox"/> Artesian Flow Rate: _____ gpm Static Water Level: _____ PH: _____ Established Well Yield: 32 gpm Water Temp: _____ F Stabilized Pumping Level _____ Stabilized Pumping Yield _____ gpm after _____ hours Comment on water quality _____ <b>WATER ZONES</b> (1) 2 gpm From 70 to _____ (2) 29 gpm From 70 to 605 (3) _____ gpm From _____ to _____ (4) _____ gpm From _____ to _____ (5) _____ gpm From _____ to _____	<b>USE DATA</b> Type of Use: <input type="checkbox"/> Drinking <input type="checkbox"/> Livestock Watering <input type="checkbox"/> Irrigation <input type="checkbox"/> Food Processing <input type="checkbox"/> Household <input type="checkbox"/> Manufacturing <input type="checkbox"/> Fire Safety <input type="checkbox"/> Cleaning <input type="checkbox"/> Recreation <input type="checkbox"/> Aestheti <input type="checkbox"/> Cooling/Heating <input type="checkbox"/> Injection Other: _____ Type of Facility: <input type="checkbox"/> Domestic <input checked="" type="checkbox"/> Public Water Supply <input type="checkbox"/> Public Institution <input type="checkbox"/> Farm <input type="checkbox"/> Industry <input type="checkbox"/> Commercial Other: _____
Screen Size and Slot for Each Zone (1) _____ inches from _____ to _____ ft. Slot Size: _____ Type: _____ Material: _____ (2) _____ inches from _____ to _____ ft. Slot Size: _____ Type: _____ Material: _____ (3) _____ inches from _____ to _____ ft. Slot Size: _____ Type: _____ Material: _____ (4) _____ inches from _____ to _____ ft. Slot Size: _____ Type: _____ Material: _____	<b>PUMP DATA</b> Type: _____ inch Series _____ gpm HP _____ Capacity _____ gpm at _____ ft. head Intake Dept _____ ft Voltage _____ Riser Pipe Size _____ Type _____ WireSize _____ Model Number _____	<b>WELLHEAD</b> Type of Well Seal/Cap: Vermin Proof Ventilated Pressure Tank _____ Location: _____ Sample Tap: _____ Measurement Port: _____ Well Vent: _____ Pressure Relief Valve: _____ Gate Valve: _____ Check Valve(if required): _____ Electrical Disconnect Switch on Power Supply: _____
Gravel Pack Size _____ From _____ to _____ ft. Size _____ From _____ to _____ ft.	<b>DISINFECTION</b> Disinfected _____ Date: _____ Disinfection Us _____ Amount: _____ Hours: _____	<b>ABANDONMENT</b> Date _____ Casing Pulled <input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A Well Disinfected _____ Type: _____ Amount: _____ (1) Grout/Backfill From _____ to _____ ft. Material: _____ (2) Grout/Backfill From _____ to _____ ft. Material: _____ (3) Grout/Backfill From _____ to _____ ft. Material: _____
Grout From 0 to 58 ft. Type: Pumped Cement From _____ to _____ ft. Type: _____	<b>LOWER CASING SEAL</b> <input type="radio"/> K-Packer <input checked="" type="radio"/> Drive Sho <input type="radio"/> Well Packer <input type="radio"/> Shale Trap 7.5 x 10 inches from 57 to 58 ft.	

Virginia Water Well Completion Report (continued)

Well Owner: Thomas Nelson  
 4004 Hunterstand Court, #102  
 Charlottesville, Va 22 VA 22911-

Permits: DEQ Permit  
 DOH Well #  
 Building Permit  
 PWSID Proposed

Well Address: 6055 Rolling Road  
 Scottsville Va 24590-

Well Location: Latitude 037°87'78.1'' N  
 Longitude 078°42'62.9'' W

Well Lot Dedicated

Size: \_\_\_\_\_ ft by: \_\_\_\_\_ ft Well House \_\_\_\_\_  
 Distance to nearest pollutant source \_\_\_\_\_ ft Type \_\_\_\_\_  
 Distance to nearest property line \_\_\_\_\_ ft Waste Disposa \_\_\_\_\_  
 Distance to Building \_\_\_\_\_ ft

Type of Well Construction

- Bored Well
- Consolidated Well
- Unconsolidated Well
- Multiple Screen Unconsolidated Well
- Abandoned Bored Well
- Abandoned Consolidated Well
- Abandoned Uncosolidated Well

Water Service Pipe

Checked under \_\_\_\_\_ p.s.i. for \_\_\_\_\_ minutes  
 Material \_\_\_\_\_ Pipe Size \_\_\_\_\_ in.  
 Installer \_\_\_\_\_ Installed Dat \_\_\_\_\_

Driller's Log

Depth (feet)		Type of Rock or Soil	Remarks
From:	To:		
0	5	Red clay	
5	20	Brown dirt and rock	
20	40	Grey soft rocky soil	
40	58	Soft rock	
58	85	Black white rock, fracture @ 70'	
85	605	Multiple fractures building to 32GPM	

I certify that the information contained herein is true and correct and that this well and/or system has been installed and constructed in accordance with the requirements for well construction as specified in compliance with appropriate county or independent city ordinances and the laws and rules of the state where the well was installed.

Signature:

Seal

Robert Royall Jr

Date: 3/23/2023

License Number 014253

**Name:** Reventon Farms Site

**Well Depth:** 600 ft bgs

**Location:** Albemarle County, VA

**Well Diameter:** 6-inch

**Logger:** Dalton Carbaugh

**Well Coordinates:** 37.877819°N, -78.42629°W



**Manager:** Thomas Nelson, P.G.

**TOC Elevation:** 503 ft amsl (approximate)

**Casing Depth:** 59 ft bgs

**Drilling Firm:** Royall Pump & Well

**Completion Date:** 3/10/2023

**Airlift Yield:** 32 gpm


**Drilling Method:** Air Rotary

**Approximate Static Water Level:** Not measured

**Water Bearing Zones:** 70-220 ft bgs (18 gpm), 300-360 ft bgs (14 gpm)

**Notes:** Surface boring 10-inch diameter. 6-inch diameter casing set to 59 ft bgs. Cement grout installed in annular space from 0-59 ft bgs.

Depth (feet)	Lithology	Lithologic Description	Well Diagram
-----------------	-----------	------------------------	--------------





## **Pavilion Well Completion Report**

\*Indicates required field or section  
 \*\*Indicates required field or section, if applicable

**1. Contact Information\***

Contact:	Name	Address	Phone
Owner	Murcielago LLC	27 Congress St, Suite 502, Salem MA 01970	
Driller	Wilson Well Drilling	P.O. Box 729, Ruckersville, Va 22968	434-990-2010
System Provider			

**2. Well Location\***

Physical Address: 6055 Rolling Rd Scottesville Va		County/City: Albemarle	
Subdivision Name:	Section:	Block:	Lot:
Tax Map/GPIN #: 124-4A			
Latitude:	N	Longitude:	W
Datum Source	Horizontal: <input type="checkbox"/> WGS84 <input type="checkbox"/> NAD83 <input type="checkbox"/> NAD27		
Lat/Long Source (Check One): <input type="checkbox"/> Map <input type="checkbox"/> GPS <input type="checkbox"/> PPDGPS <input type="checkbox"/> Survey <input type="checkbox"/> Imagery <input type="checkbox"/> WAAS			
Location Information Collected By :			
Physical Location Description:			

**3. Facility & Use\***

Type of Facility (Check One):	Type of Use (Check All That Apply):
<input checked="" type="checkbox"/> Private <input type="checkbox"/> Waterworks <input type="checkbox"/> Observation/Monitoring Well	<input checked="" type="checkbox"/> Drinking/Domestic Use <input type="checkbox"/> Manufacturing <input type="checkbox"/> Geothermal (Cooling/Heating) <input type="checkbox"/> Closed <input type="checkbox"/> Open: <input type="checkbox"/> Returned to Surface <input type="checkbox"/> Returned to Aquifer <input type="checkbox"/> Agricultural <input type="checkbox"/> Irrigation <input type="checkbox"/> Fire Safety <input type="checkbox"/> Food Processing <input type="checkbox"/> Injection

**4. Well Construction\***

Well designation, Name or Number:			
Date Started: 9/9/19	Date Completed: 9/9/19	Type Rig: Rotary	
Class Well (Check One): <input type="checkbox"/> I <input type="checkbox"/> IIA <input type="checkbox"/> IIB <input type="checkbox"/> IIIA <input checked="" type="checkbox"/> IIIB <input type="checkbox"/> IIIC <input type="checkbox"/> IIID <input type="checkbox"/> IIIE <input type="checkbox"/> IV			
Construction Type (Check One): <input checked="" type="checkbox"/> New <input type="checkbox"/> Existing-Modified: <input type="checkbox"/> Well <input type="checkbox"/> Pump: Date _____			
Well Depth: 420 ft.	Total Hole (borehole) Depth: 420 ft.	Depth to Bedrock: _____ ft.	
Hole Size (Include reamed zones): 6 inches from 0 to 420 ft. Inches from _____ to _____ ft.			
Height of Casing above Land Surface: _____ ft. 18 inches			
Casing Size (I.D.) and Materials: (below)		Total Depth of Casing: 56 ft.	
_____ inches from _____ to _____ ft. <input type="checkbox"/> infilled	Material	Weight per ft.	or wall thickness in.
_____ inches from _____ to _____ ft. <input type="checkbox"/> infilled	Material	Weight per ft.	or wall thickness in.
_____ inches from _____ to _____ ft. <input type="checkbox"/> infilled	Material	Weight per ft.	or wall thickness in.
Screen Size & Mesh:			
_____ inches from _____ to _____ ft. <input type="checkbox"/> infilled	Mesh Size	Type	
_____ inches from _____ to _____ ft. <input type="checkbox"/> infilled	Mesh Size	Type	
_____ inches from _____ to _____ ft. <input type="checkbox"/> infilled	Mesh Size	Type	
Water Zones: from 77 to 78 ft.		from 219 to 221 ft.	from 400 to 401 ft.
Gravel Pack:			
Size: _____ Type: _____	from _____ to _____ ft.	Size: _____ Type: _____	from _____ to _____ ft.
Grout Type: <input checked="" type="checkbox"/> Bentonite Slurry <input type="checkbox"/> Neat Cement <input type="checkbox"/> Bentonite pellets/chips <input type="checkbox"/> Concrete <input type="checkbox"/> Neat Cement (6% bentonite)	from 0 to 50 ft.  from _____ to _____ ft.	Grouting Method: <input type="checkbox"/> Poured from surface <input type="checkbox"/> Poured through tremmie pipe <input checked="" type="checkbox"/> Pumped from bottom upward	Type of Seal: <input checked="" type="checkbox"/> pitless adapter <input type="checkbox"/> sanitary seal
Camera Survey: <input type="checkbox"/> Yes <input type="checkbox"/> No			Date Conducted:
Additional Well Construction Form Information Attached: <input type="checkbox"/> Yes <input type="checkbox"/> No			

Well designation, Name or Number\*: \_\_\_\_\_

**5. Disinfection**

Well Disinfected: <input type="checkbox"/> Yes <input type="checkbox"/> No	Date: _____
----------------------------------------------------------------------------	-------------

**6. Abandonment** (\*When abandoning the well, Sections 1 thru 4 must be completed and/or attach original GW-2)

Date Started: _____	Date Completed: _____
Static Water Level (unpumped level measured): _____	ft.
Casing Size (I.D.) and Materials: _____	Casing Pulled: <input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Uncased Well
Depth of Fill: _____	Type and Source of Fill: _____
Grout: From _____ to _____ Type: _____	From _____ to _____ Type: _____
Method of permanently marking location: _____	

**7. Pump Test\*\***

Static Water Level (unpumped level measured): 40	ft.
Date: _____	Method (Check One): <input type="checkbox"/> Water Tape <input type="checkbox"/> Airline <input type="checkbox"/> Transducer <input type="checkbox"/> Other
Stabilized measured pumping water level: _____	ft.
Date: _____	Method (Check One): <input type="checkbox"/> Top of Well <input type="checkbox"/> Top of Casing <input type="checkbox"/> Surface Level
Test Pump Intake Depth: _____	ft
Natural Flow: <input type="checkbox"/> Yes <input type="checkbox"/> No	Flow Rate 7 gpm
Estimated Well Yield: _____	gpm
Stabilized Yield: _____	gpm after _____ hours

**8. Pump Data\*\***

Type: <input type="checkbox"/> submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Shallow Jet <input type="checkbox"/> Deep Jet <input type="checkbox"/> Other: _____	Motor HP: _____
Production Pump Intake Depth: _____	ft
Rated Capacity: _____	gpm at _____ ft TDH

**9. Geologic Information**

Type Logs: _____	Aquifer Test Performed: _____
Water Quality Results Attached: Yes <input type="checkbox"/> No <input type="checkbox"/>	

Comments:

Formation _____	Lithology _____	Province _____	Geologic Map Used _____
Elevation _____			
<b>For Office Use</b>			

COMMONWEALTH OF VIRGINIA  
 UNIFORM WATER WELL COMPLETION REPORT

DEQ Well # \_\_\_\_\_  
 USGS Local # \_\_\_\_\_  
 VDH HDIN # \_\_\_\_\_  
 VDH PWSID # \_\_\_\_\_

\*Indicates required field or section  
 \*\*Indicates required field or section, if applicable

**10. Driller's Log** (Use additional sheets if necessary)\*

Well designation, Name or Number:					
Depth (feet)		Type of Rock or Soil	Remarks	Drilling Time (Min.)	Diagram of Well Construction (with dimensions)
From	To	(Color, material, fossils, hardness, etc.)	(Water, caving, cavities, etc.)		
0	52	Sandy Soil & Sandstone			
52	70	Brown Shale			
70	219	Blue Shale			
219	221	Brown Shale Streak			
221	420	Blue Shale			

**11. Certification**

*I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, the information submitted is to the best of my knowledge and belief true, accurate, and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment for knowing violations.*

Signature\*:  Date: 9/30/19

License Number: 2719000751

\*Indicates required field or section  
 \*\*Indicates required field or section, if applicable

## Additional Well Construction Data

(Use and submit only if additional space is needed)

### 12. Additional Well Construction Data


<b>Well designation, Name or Number:</b>											
<b>Physical Location:</b>				<b>Date Started:</b>				<b>Date Completed:</b>			
<b>Hole Size (Include reamed zones):</b>											
inches	from	to	ft.	inches	from	to	ft.	inches	from	to	ft.
inches	from	to	ft.	inches	from	to	ft.	inches	from	to	ft.
inches	from	to	ft.	inches	from	to	ft.	inches	from	to	ft.
<b>Casing Size (I.D.) and Materials:</b>											
inches	from	to	ft.	<input type="checkbox"/> infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	<input type="checkbox"/> infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	<input type="checkbox"/> infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	<input type="checkbox"/> infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	<input type="checkbox"/> infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	<input type="checkbox"/> infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	<input type="checkbox"/> infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	<input type="checkbox"/> infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	<input type="checkbox"/> infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	<input type="checkbox"/> infilled	Material	Weight per ft.	or wall thickness	in.			
<b>Screen Size &amp; Mesh:</b>											
inches	from	to	ft.	<input type="checkbox"/> infilled	Mesh Size	Type					
inches	from	to	ft.	<input type="checkbox"/> infilled	Mesh Size	Type					
inches	from	to	ft.	<input type="checkbox"/> infilled	Mesh Size	Type					
inches	from	to	ft.	<input type="checkbox"/> infilled	Mesh Size	Type					
inches	from	to	ft.	<input type="checkbox"/> infilled	Mesh Size	Type					
inches	from	to	ft.	<input type="checkbox"/> infilled	Mesh Size	Type					
inches	from	to	ft.	<input type="checkbox"/> infilled	Mesh Size	Type					
inches	from	to	ft.	<input type="checkbox"/> infilled	Mesh Size	Type					
inches	from	to	ft.	<input type="checkbox"/> infilled	Mesh Size	Type					
inches	from	to	ft.	<input type="checkbox"/> infilled	Mesh Size	Type					
<b>Water Zones:</b>											
From	to	ft.	From	to	ft.	From	to	ft.	From	to	ft.
From	to	ft.	From	to	ft.	From	to	ft.	From	to	ft.
From	to	ft.	From	to	ft.	From	to	ft.	From	to	ft.
From	to	ft.	From	to	ft.	From	to	ft.	From	to	ft.
<b>Gravel Pack:</b>											
Size:	Type:	From	to	ft.	Size:	Type:	From	to	ft.		
Size	Type:	From	to	ft.	Size:	Type:	From	to	ft.		
Size:	Type:	From	to	ft.	Size:	Type:	From	to	ft.		
<b>Grout Type:</b>				from	to	ft.	<b>Grouting Method:</b>				
<input type="checkbox"/> Bentonite Slurry				<input type="checkbox"/> Neat Cement		from	to	ft.	<input type="checkbox"/> Poured from surface		
<input type="checkbox"/> Bentonite pellets/chips				<input type="checkbox"/> Concrete		from	to	ft.	<input type="checkbox"/> Poured through tremmie pipe		
<input type="checkbox"/> Neat Cement (6% bentonite)				from	to	ft.	<input type="checkbox"/> Pumped from bottom upward				

## **Appendix B**

### **Red Barn Well & Well B Step-Drawdown Test Data Plots**

**Red Barn Well Step-Drawdown Pumping Test Plots**  
*(test performed prior to construction modification)*

### Red Barn Well Step-Drawdown Pumping Test Data (data collected prior to modification of the well)




Graph B-1: Red Barn Well step-drawdown pumping test data. The test was performed prior to the well's casing modification and deepening in April 2023.





Graph B-2: Red Barn Well step-drawdown pumping test data on a per step basis. The test was performed prior to the well's casing modification and deepening in April 2023.

## **Well B Step-Drawdown Pumping Test Plots**



Graph B-3: Well B step-drawdown pumping test data.



Graph B-4: Well B step-drawdown pumping test data on a per step basis.

**Appendix C**

**Wells A & B VDH-ODW Site Approval Letter**



# COMMONWEALTH of VIRGINIA

DEPARTMENT OF HEALTH

## OFFICE OF DRINKING WATER

Lexington Field Office

131 Walker Street  
Lexington, VA 24450  
Phone: 540-463-7136  
Fax: 540-463-3892

SUBJECT: Albemarle County  
Waterworks: Reventon Farms  
PWSID No: Proposed

January 11, 2023

Mr. Thomas P. Nelson, P.G.  
ECS Mid-Atlantic, LLC  
4004 Hunterstand Court, #102  
Charlottesville, VA 22911

Dear Mr. Nelson:

This letter provides the results of our December 21, 2022 inspection of the proposed well sites to serve Reventon Farms located in Albemarle County, Virginia. In accordance with the *Waterworks Regulations*, the following well site is tentatively approved by the Virginia Department of Health Office of Drinking Water (VDH-ODW) for the construction of a well to be utilized as a public drinking water supply:

### Site 1 (WL001) & Site 2 (WL002)

The approval of the well site listed above expires 12 months from the date of this letter, and is subject to the conditions described in the attached Well Site Approval Conditions Form. This approval is limited to well drilling, casing, grouting, and testing of the well. If drilling of any well listed above has not commenced by the expiration date, a re-inspection of the well site is required.

Upon receipt of the required documentation and after plans and specifications have been approved, a Construction Permit will be issued by the State Health Commissioner in accordance with the *Waterworks Regulations*. Construction of the waterworks facilities shall not be started until the construction permit has been issued.

Some counties require a local well drilling permit and have other requirements that are in addition to those outlined in this letter or required by the Virginia Waterworks Regulations, and it is your responsibility to comply with the local requirements. Please contact the county health department and planning/zoning office before drilling the well.

Waterworks wells must be constructed by a Water Well Systems Provider certified by the Virginia Department of Professional and Occupational Regulation (DPOR). You may confirm licensure status by contacting DPOR or using the search tool on DPOR's website at the following address:

<http://www.dpor.virginia.gov/LicenseLookup/>.

Mr. Thomas P. Nelson, P.G.  
Page 2 of 2

SUBJECT: Albemarle County  
Waterworks: Reventon Farms  
PWSID No: Proposed

Construction and development of waterworks wells must follow specific procedures. Please refer to the conditions below and our website at <https://www.vdh.virginia.gov/drinking-water/permits-and-design/well-development-procedures/> for details.

A Preliminary Source Water Assessment (PreSWA) has been compiled for the proposed well. Attached you will find inventory, maps and summaries of land use and potential sources of contamination within the assessment area of the proposed well. Please take the time to review this information and contact me if you have any questions or corrections. This information may be used to generate a Source Water Protection Plan if desired. For assistance developing a Source Water Protection Plan, please contact [sourcewater@vdh.virginia.gov](mailto:sourcewater@vdh.virginia.gov).

Upon request, an electronic version of the Preliminary Source Water Assessment information may be emailed to you. If you or your consultant has GIS software, we can also provide a geodatabase to facilitate further work with the data. To learn more about our Source Water Assessment and Protection Programs, as well as eligibility for assistance and funding opportunities to implement source water protection measures, we encourage you to visit our website at the following address: <http://www.vdh.virginia.gov/ODW/SourceWaterPrograms/index.htm>.

Please contact Environmental Health Technical Specialist James Simmons at (540) 463-0413, or at [James.simmons@vdh.virginia.gov](mailto:James.simmons@vdh.virginia.gov) if you have further questions.

Sincerely,



Steven J. Kvech, PE  
Deputy Field Director

SJK/JWS/kk/230103-2

Enclosures:

Well Approval Conditions Form  
Preliminary Source Water Assessments

cc: Albemarle County Health Department  
Albemarle County Executive  
Albemarle County Building Official

**WELL APPROVAL CONDITIONS FORM**

Approved Well(s)	Site #1 WL001	Site #2 WL002	-	-
Location:	Latitude:	37.87254° N	37.877819° N	-
	Longitude:	78.424837° W	78.42629° W	-
	Marked:	Orange Flag	-	-
Well Construction Class:	Class II. Refer to <i>Waterworks Regulations</i> 12VAC5-590-840 F.			
Approval Expiration Date:	January 11, 2024 If drilling of the well has not commenced by this date, re-inspection of the well site is required.			
Well Lot Characteristics:	Minimum distance of 50 feet between the well and all potential sources of contamination, property lines, and rights-of-way or easements on the property. Refer to <i>Waterworks Regulations</i> Sections 12VAC5-590-840 D & E. See attached (sketch, topographic map, photo, etc.).			
	The well lot must be graded as necessary to divert surface run-off from the well and to prevent ponding on the well lot.			
	The well must be located higher than the 100-year flood elevation or a lower elevation may be considered if it can be adequately shown that the well can be protected from flooding.			
Grouting:	Use neat cement grout, in accordance with <i>Waterworks Regulations</i> Section 12VAC5-590-840 G 5. Notify this office of the date and time that the well will be grouted. Provide this information as soon as possible so that a member of our staff may be present during grouting.			
Well Capacity Test	A yield and drawdown test must be run for at least: approved reduced time (no less than 24 hours) for noncommunity waterworks requiring 3 gpm or less over normal hours of operation. We recommended the pumping rate be controlled throughout the test to maximize the production from the well and to produce a stabilized pump water level for at least the last 6 hours of the yield test. Immediately following the yield and drawdown test the water level recovery in the well should be recorded for no less than 6 hours or until the well returns to its static water level, whichever occurs first. If water will discharge into streams during pumping tests, please contact the Department of Environmental Quality Valley Regional Office to determine if a discharge permit is required.			
Simultaneous Testing Required:	Not applicable, provided that all existing wells on the property will be properly abandoned per the <i>Waterworks Regulations</i> .			



Well in Groundwater Management Area:	Not Applicable.
Required Bacteriological, Chemical, and Physical Sampling:	<p>A series of twenty bacteriological samples must be collected from the well discharge and submitted to a certified laboratory (DCLS or private laboratory) in order to determine the bacteriological quality of the raw groundwater.</p> <p>One bacteriological sample should be collected at minimum fifteen-minute intervals during the last five hours of the yield and drawdown test.</p> <p>Water samples must be collected and analyzed for nitrate + nitrite (combined) and nitrite-N. It is recommended that samples be analyzed for inorganic contaminants and metals also, to determine if water will result in objectionable taste, odor, color, or cause corrosion or calcium build up.</p>
Submittals Required Prior to Issuance of Construction Permit:	<p>Uniform Water Well Completion Report (Form GW-2) and schematic drawing(s) of well construction.</p> <p>Well yield, drawdown, and well recovery test results.</p> <p>Results of required bacteriological and chemical sampling (if not reported directly by laboratory).</p> <p>Construction permit application.</p> <p>Final construction plans and specifications, including design calculations, prepared by a licensed professional engineer. A Preliminary Engineering Report may be required prior to submission of final construction documents.</p> <p>Plans for construction permits for transient non-community waterworks may be exempt from the Professional Engineer licensure requirements under certain conditions.</p>

PWSID: 2000000  
 Source ID: WL001  
 Facility: WL001  
 Waterworks: Reventon Farms

# Swap Zone 1

Date: 1/3/2023

TINWSF\_IS: 0.0  
 Jurisdiction: Albemarle  
 District:



All data is collected from multiple agencies using various collection methods. VDH does not guarantee the location and accuracy of these data and these data is intended as a reference source only. Map is projected in NAD\_1983\_Lambert\_Conformal\_Conic, scale and distances are approximate.



- |             |             |                     |                |                           |                                    |                        |
|-------------|-------------|---------------------|----------------|---------------------------|------------------------------------|------------------------|
| ✕ Source    | 500 Year    | Other PSC           | Marinas        | ◆ Petroleum Tank - Active | — Rails                            | ▨ Impaired Waterbodies |
| ● Intake    | Streams     | ⊗ Mines - Other     | ⊗ Landfills    | ◆ Petroleum Tank - Closed | — Petroleum Pipeline               | ▭ Karst Area           |
| ⊕ Well      | Contours    | ⊗ Mines - Abandoned | ⊗ Industrial   | ⊗ Boat Ramps              | — Natural Gas Pipeline             |                        |
| ⊕ GUDIS     | Waterbodies | ⊗ Mines - Active    | ⊗ Hospitals    | ⊗ Airports                | — Electric Power Transmission Line |                        |
| Floodplains |             | ⊗ Injection Wells   | ⊗ RCRA         | ⊗ Oil Gas Wells           | Zone 1                             |                        |
| 100 Year    |             | ⊗ Tire Piles        | ⊗ Golf Courses | — Impaired Streams        | Zone 2                             |                        |
|             |             | ⊗ Superfund         | ⊗ NPDES        | — Roads                   |                                    |                        |

PWSID: 2000000

Source ID: WL001

Facility: WL001

Waterworks: Reventon Farms

# SWAP Zone 2

Date: 1/3/2023

TINWSF\_IS: 0.0

Jurisdiction: Albemarle

District:



All maps are collected from multiple agencies using various collection methods. VDH does not guarantee the location and accuracy of these data and these data is intended as a reference source only. Map is projected in NAD\_1983\_Lambert\_Conformal\_Conic, scale and distance are approximate.



- |             |             |                   |              |                         |                                  |                      |
|-------------|-------------|-------------------|--------------|-------------------------|----------------------------------|----------------------|
| Source      | 500 Year    | Other PSC         | Marinas      | Petroleum Tank - Active | Rails                            | Impaired Waterbodies |
| Intake      | Streams     | Mines - Other     | Landfills    | Petroleum Tank - Closed | Petroleum Pipeline               | Karst Area           |
| Well        | Contours    | Mines - Abandoned | Industrial   | Boat Ramps              | Natural Gas Pipeline             |                      |
| GUDIS       | Waterbodies | Mines - Active    | Hospitals    | Airports                | Electric Power Transmission Line |                      |
| Floodplains |             | Injection Wells   | RCRA         | Oil Gas Wells           | Zone 1                           |                      |
| 100 Year    |             | Tire Piles        | Golf Courses | Impaired Streams        | Zone 2                           |                      |
|             |             | Superfund         | NPDES        | Roads                   |                                  |                      |


PWSID: 2000000  
 Source ID: WL001  
 Facility: WL001  
 Waterworks: Reventon Farms

# SWAP Zone 2 Land Use

Date: 1/3/2023

TINWSF\_IS: 0.0  
 Jurisdiction: Albemarle  
 District:

0 510 1,020 FT



All data is collected from multiple agencies using various collection methods. VDH does not guarantee the location and accuracy of these data and these data is intended as a reference source only. Map is projected in NAD\_1983\_Lambert\_Conformal\_Conic, scale and distances are approximate.



- ✕ Source
- Intake
- ⊕ Well
- ⊕ GUDIS
- ☐ Zone 1
- ☐ Zone 2

- Roads
- Rails
- Impaired Streams
- Streams
- Contours
- Impaired Waterways
- Waterbodies

### Land Use

- Additional Extracted Impervious
- Barren
- Crop
- Forest Harvest
- Hardwood Forest/Pine Forest/Mixed Forest
- Local Buildings/Roads/Pavement
- Pasture
- Scrub
- Trees
- Turf/Grass
- Water
- Wetland

Potential Sources of Contamination Inventory

County/City: Albemarle      Waterworks: Reventon Farms      PWSID: 2000000      Source ID: WL001      Facility: WL001

Evaluated by: \_\_\_\_\_      Date: \_\_\_\_\_      Reviewed by: \_\_\_\_\_      Date: \_\_\_\_\_

Map ID      Distance to Source (miles)      Contaminant Type      Facility Type      Property Owner/Business Name      Mailing Address/Location


POTENTIAL SOURCES OF CONTAMINATION SUMMARY

County\City: Albemarle

PWSID: 2000000

Source ID: WL001

Facility: WL001

Waterworks: Reventon Farms

Facility Type	Zone 1 Count	Zone 2 Count	Total
Sum	0	0	0

PWSID: 2000000  
 Source ID: WL002  
 Facility: WL002  
 Waterworks: Reventon Farms

# Swap Zone 1

Date: 1/3/2023

TINWSF\_IS: 0.0  
 Jurisdiction: Albemarle  
 District:



All data is collected from multiple agencies using various collection methods. VDH does not guarantee the location and accuracy of these data and these data is intended as a reference source only. Map is projected in NAD\_1983\_Lambert\_Conformal\_Conic, scale and distances are approximate.




- |             |             |                   |              |                         |                                  |                      |
|-------------|-------------|-------------------|--------------|-------------------------|----------------------------------|----------------------|
| Source      | 500 Year    | Other PSC         | Marinas      | Petroleum Tank - Active | Rails                            | Impaired Waterbodies |
| Intake      | Streams     | Mines - Other     | Landfills    | Petroleum Tank - Closed | Petroleum Pipeline               | Karst Area           |
| Well        | Contours    | Mines - Abandoned | Industrial   | Boat Ramps              | Natural Gas Pipeline             |                      |
| GUDIS       | Waterbodies | Mines - Active    | Hospitals    | Airports                | Electric Power Transmission Line |                      |
| Floodplains |             | Injection Wells   | RCRA         | Oil Gas Wells           | Zone 1                           |                      |
| 100 Year    |             | Tire Piles        | Golf Courses | Impaired Streams        | Zone 2                           |                      |
|             |             | Superfund         | NPDES        | Roads                   |                                  |                      |

PWSID: 2000000  
 Source ID: WL002  
 Facility: WL002  
 Waterworks: Reventon Farms

# SWAP Zone 2

Date: 1/3/2023

TINWSF\_IS: 0.0  
 Jurisdiction: Albemarle  
 District:



All data is collected from multiple agencies using various collection methods. VDH does not guarantee the location and accuracy of these data and these data is intended as a reference source only. Map is projected in NAD\_1983\_Lambert\_Conformal\_Conic, scale and distance are approximate.



- |                      |                      |                   |              |                         |                                  |                      |
|----------------------|----------------------|-------------------|--------------|-------------------------|----------------------------------|----------------------|
| ✕ Source             | 500 Year Floodplains | Other PSC         | Marinas      | Petroleum Tank - Active | Rails                            | Impaired Waterbodies |
| ● Intake             | Streams              | Mines - Other     | Landfills    | Petroleum Tank - Closed | Petroleum Pipeline               | Karst Area           |
| ● Well               | Contours             | Mines - Abandoned | Industrial   | Boat Ramps              | Natural Gas Pipeline             |                      |
| ● GUDIS              | Waterbodies          | Mines - Active    | Hospitals    | Airports                | Electric Power Transmission Line |                      |
| Floodplains          |                      | Injection Wells   | RCRA         | Oil Gas Wells           | Zone 1                           |                      |
| 100 Year Floodplains |                      | Tire Piles        | Golf Courses | Impaired Streams        | Zone 2                           |                      |
|                      |                      | Superfund         | NPDES        | Roads                   |                                  |                      |




PWSID: 2000000  
 Source ID: WL002  
 Facility: WL002  
 Waterworks: Reventon Farms

# SWAP Zone 2 Land Use

Date: 1/3/2023

TINWSF\_IS: 0.0  
 Jurisdiction: Albemarle  
 District:

0 510 1,020 FT



All data is collected from multiple agencies using various collection methods. VDH does not guarantee the location and accuracy of these data and these data is intended as a reference source only. Map is projected in NAD\_1983\_Lambert\_Conformal\_Corke, scale and distances are approximate.



- ✕ Source
- Intake
- ⊕ Well
- ⊕ GUDIS
- ☐ Zone 1
- ☐ Zone 2

- Roads
- Rails
- Impaired Streams
- Streams
- Contours
- Impaired Waterways
- Waterbodies

### Land Use

- Additional Extracted Impervious
- Barren
- Crop
- Forest Harvest
- Hardwood Forest/Pine Forest/Mixed Forest
- Local Buildings/Roads/Pavement
- Pasture
- Scrub
- Trees
- Turf/Grass
- Water
- Wetland

Potential Sources of Contamination Inventory

County/City: Albemarle      Waterworks: Reventon Farms      PWSID: 2000000      Source ID: WL002      Facility: WL002

Evaluated by: \_\_\_\_\_ Date: \_\_\_\_\_ Reviewed by: \_\_\_\_\_ Date: \_\_\_\_\_

Map ID    Distance to Source (miles)    Contaminant Type    Facility Type    Property Owner/Business Name    Mailing Address/Location


POTENTIAL SOURCES OF CONTAMINATION SUMMARY

County\City: Albemarle

PWSID: 2000000

Source ID: WL002

Facility: WL002

Waterworks: Reventon Farms

Facility Type	Zone 1 Count	Zone 2 Count	Total
Sum	0	0	0

## **Appendix D**

### **Information about Properties Located Within 1,000 Feet of the Subject Site**

## Well Locations on Offsite Properties within 1,000 Feet of the Subject Site

Offsite Property Address	Property County Location	Well Distance from Nearest Subject Site Supply Well (feet)	Nearest Subject Site Supply Well
6089 Rolling Rd S	Fluvanna	350	Red Barn Well
6018 Rolling Rd S	Fluvanna	420	Red Barn Well
6066 Rolling Rd S	Fluvanna	460	Red Barn Well
5978 Rolling Rd S	Fluvanna	500	Red Barn Well
6133 Rolling Rd S	Fluvanna	520	Red Barn Well
6167 Rolling Rd S	Fluvanna	680	Red Barn Well
5890 Rolling Rd S	Fluvanna	700	Red Barn Well
5922 Rolling Rd S	Fluvanna	730	Red Barn Well
151 Blue Mountain Ln	Fluvanna	910	Red Barn Well
5842 Rolling Rd S	Fluvanna	1,070	Red Barn Well
6224 Rolling Rd S	Fluvanna	1,210	Red Barn Well
6278 Rolling Rd S	Fluvanna	1,320	Red Barn Well
5826 Rolling Rd S	Fluvanna	1,320	Red Barn Well
6285 Rolling Rd S	Fluvanna	1,330	Red Barn Well
144 Blue Mountain Ln	Fluvanna	1,400	Red Barn Well
5750 Rolling Rd S	Fluvanna	1,520	Red Barn Well
5738 Rolling Rd S	Fluvanna	1,580	Red Barn Well
5696 Rolling Rd S	Fluvanna	1,740	Red Barn Well
1421 Little Wyoming Ln	Albemarle	1,830	Well B
6826 Rolling Rd S	Fluvanna	1,870	Well B
5668 Rolling Rd S	Fluvanna	1,920	Red Barn Well
6876 Rolling Rd S	Fluvanna	1,940	Well B
6294 Rolling Rd S	Fluvanna	1,940	Red Barn Well
6992 Rolling Rd S	Albemarle/Fluvanna	2,080	Well B
55 Blueberry Hill Dr	Albemarle/Fluvanna	2,110	Well B
6692 Rolling Rd S	Fluvanna	2,110	Well B
5542 Rolling Rd	Albemarle	2,180	Well B
7022 Rolling Rd S	Albemarle/Fluvanna	2,190	Well B
5540 Rolling Rd	Albemarle	2,310	Well B
6652 Rolling Rd S	Fluvanna	2,320	Well B
6804 Rolling Rd S	Fluvanna	2,360	Well B
7058 Rolling Rd S	Albemarle/Fluvanna	2,390	Well B
7084 Rolling Rd S	Albemarle/Fluvanna	2,420	Well B
5600 Rolling Rd	Albemarle	2,440	Well B
5572 Rolling Rd S	Fluvanna	2,450	Red Barn Well
6512 Rolling Rd S	Fluvanna	2,530	Red Barn Well
5578 Rolling Rd	Albemarle	2,630	Well B
6422 Rolling Rd S	Fluvanna	2,650	Red Barn Well
5566 Rolling Rd	Albemarle	2,720	Well B
8 Ruritan Lake Rd	Albemarle/Fluvanna	2,770	Well B

16 Ruritan Lake Rd	Albemarle/Fluvanna	2,860	Well B
5518 Rolling Rd S	Fluvanna	2,880	Red Barn Well
25 Ruritan Lake Rd	Albemarle/Fluvanna	2,990	Well B
22 Ruritan Lake Rd	Albemarle/Fluvanna	3,000	Well B
6798 Rolling Rd S	Fluvanna	3,020	Well B
250 Blueberry Hill Dr	Fluvanna	3,080	Well B
26 Ruritan Lake Rd	Albemarle/Fluvanna	3,120	Well B
5575 Rolling Rd	Albemarle	3,190	Well B
5563 Rolling Rd	Albemarle	3,200	Well B
5438 Rolling Rd S	Fluvanna	3,270	Red Barn Well
34 Ruritan Lake Rd	Albemarle/Fluvanna	3,300	Well B
187 Briery Creek Rd	Fluvanna	3,300	Red Barn Well
40 Ruritan Lake Rd	Fluvanna	3,410	Well B
139 Briery Creek Rd	Fluvanna	3,430	Red Barn Well
42 Ruritan Lake Rd	Fluvanna	3,490	Well B
45 Briery Creek Rd	Fluvanna	3,540	Red Barn Well
5352 Rolling Rd S	Fluvanna	3,750	Red Barn Well
5303 Rolling Rd S	Fluvanna	3,920	Red Barn Well
145 Branch Rd	Fluvanna	4,050	Red Barn Well
5266 Rolling Rd S	Fluvanna	4,110	Red Barn Well
509 Briery Creek Rd	Fluvanna	4,180	Red Barn Well
53 Branch Rd	Fluvanna	4,310	Red Barn Well
2349 Moore Ln	Albemarle	4,330	Well B
111 Branch Rd	Fluvanna	4,440	Red Barn Well
5171 Rolling Rd S	Fluvanna	4,520	Red Barn Well
1556 Briery Creek Rd	Albemarle	7,450	Red Barn Well

## **Appendix E**

### **Available Well Records of Proximal Offsite Properties**

Ed-  
962-9857

1421 Little Wyoming Ln.

HANSON

Commonwealth of Virginia  
Uniform Water Well Completion Report

Owner Taylor Lyn Homes Tax Map ID \_\_\_\_\_  
Address \_\_\_\_\_ VDH Permit \_\_\_\_\_  
Phone \_\_\_\_\_ VWCB Permit \_\_\_\_\_  
Location Woodridge Est. VWCB ID \_\_\_\_\_  
County \_\_\_\_\_

\*Well Data\*

General Information

Drilling Method Kotary Date Completed 8/13/97 Total Depth of Well 230  
Depth to Bedrock 160 Yield 8 (GPM) Length of Test \_\_\_\_\_  
Static Water Level 30 Stabilized Water Level \_\_\_\_\_ Natural Flow (Rate) 8 GPM  
Well Disinfected (YorN) \_\_\_\_\_ Disinfectant Used \_\_\_\_\_ Amount Used \_\_\_\_\_

Casing

From 0 to 67 From \_\_\_\_\_ to \_\_\_\_\_  
Size 1 1/4 Material PRC Size \_\_\_\_\_ Material \_\_\_\_\_  
Weight/Schedule PRC Weight/Schedule \_\_\_\_\_ Weight/Schedule \_\_\_\_\_

Gravel Pack

From \_\_\_\_\_ to \_\_\_\_\_ From \_\_\_\_\_ to \_\_\_\_\_  
From \_\_\_\_\_ to \_\_\_\_\_

Grout

From 0 to 50 From \_\_\_\_\_ to \_\_\_\_\_  
Bore Hole Size 10 Bore Hole Size \_\_\_\_\_  
Type Bentonite Type \_\_\_\_\_  
Method Pump Method \_\_\_\_\_

Water Zones or Screened Intervals

From 110 to 111 From \_\_\_\_\_ to \_\_\_\_\_  
Mesh Size \_\_\_\_\_ Diam. \_\_\_\_\_ Mesh Size \_\_\_\_\_ Diam. \_\_\_\_\_  
From \_\_\_\_\_ to \_\_\_\_\_ From \_\_\_\_\_ to \_\_\_\_\_  
Mesh Size \_\_\_\_\_ Diam. \_\_\_\_\_ Mesh Size \_\_\_\_\_ Diam. \_\_\_\_\_

\*Use Data\*

Private Well: Domestic  Agricultural \_\_\_\_\_ Industrial \_\_\_\_\_ Monitoring \_\_\_\_\_  
Public Well: Community \_\_\_\_\_ Non Community \_\_\_\_\_

RECEIVED

NOV 17 1997

ENVIRONMENTAL HEALTH



Drillers Log.  
(Use additional sheets if necessary)

Depth	Description of Formation or Sediment	Remarks
0-10	Red Clay	
10-40	Sandy Soil	
40-60	Brown Shale	
60-230	Blue Shale	

I certify that the information contained here is true and that this well was installed and constructed in accordance with the permit and further that the well complies with all applicable state and local regulations, ordinances and laws.

Drilling

Contractor Wilson Well & Pump Co.

Address 109 Buck Mtn. Rd.

Earlysville, Va. 22936

Phone 974-1982

Drillers Signature Joe Wilson

Date 8/13/97

Representing Wilson Well & Pump Co.

Virginia Contractors License Number 2705-028506

### 5600 Rolling Rd. South

#### Commonwealth of Virginia Uniform Water Well Completion Report

Owner: Bailey Meade Homes

Tax Map ID# 118-116T

Address: 140 S Pantops Dr suite 200  
Charlottesville VA 22911

VDH Permit # 101-07-0642

Phone: 434-977-8882

WWCB#: \_\_\_\_\_

Location: Woodridge Estates  
lot 21

County: Albemarle

#### \*Well Data\*

##### General Information

Drilling Method: Rotary  
Depth to Bedrock: 86  
Static Water Level: 40  
Well Disinfected: \_\_\_\_\_

Date Completed: 12/27/07 Total Depth: 320  
Yield: 3 Length of Test: 1hr  
Stabilized Water Level: \_\_\_\_\_ Natural Flow: 3  
Disinfectant Used: \_\_\_\_\_ Amount Used: \_\_\_\_\_

##### Casing

From: 0 to 91  
Size: 6 1/4 Material: D/C  
Weight/Schedule: 80

From: \_\_\_\_\_ to \_\_\_\_\_  
Size: \_\_\_\_\_ Material: \_\_\_\_\_  
Weight/Schedule: \_\_\_\_\_

##### Gravel Pack

From: \_\_\_\_\_ to \_\_\_\_\_

From: \_\_\_\_\_ to \_\_\_\_\_

From: \_\_\_\_\_ to \_\_\_\_\_

##### Grout

From 0 to 20  
Bore Hole Size: 10"  
Type: Bentonite  
Method: pump

From \_\_\_\_\_ to \_\_\_\_\_  
Bore Hole Size: \_\_\_\_\_  
Type: \_\_\_\_\_  
Method: \_\_\_\_\_

From \_\_\_\_\_ to \_\_\_\_\_  
Bore Hole Size: \_\_\_\_\_  
Type: \_\_\_\_\_  
Method: \_\_\_\_\_

##### Water Zones or Screened Intervals

From 135 to 140  
Mesh Size \_\_\_\_\_ Diam \_\_\_\_\_  
From \_\_\_\_\_ to \_\_\_\_\_  
Mesh Size \_\_\_\_\_ Diam \_\_\_\_\_

From \_\_\_\_\_ to \_\_\_\_\_  
Mesh Size \_\_\_\_\_ Diam \_\_\_\_\_  
From \_\_\_\_\_ to \_\_\_\_\_  
Mesh Size \_\_\_\_\_ Diam \_\_\_\_\_

Private Well: Domestic  Agricultural \_\_\_\_\_ Industrial \_\_\_\_\_ Monitoring \_\_\_\_\_  
Public Well: Community \_\_\_\_\_ Non-Community \_\_\_\_\_

# RECEIVED

JAN 02 2008

*J. Baker*  
ENVIRONMENTAL HEALTH

## Driller's Log

0-10	Red Clay	
10-30	yellow sand	
30-60	Brown sand	
60-90	yellow + brown sand	
90-320	Blue + white rock	

I certify that the information contained here is true and that this well was installed and constructed in accordance with the permit and further that the well complies with all applicable state and local regulations, ordinances, and laws.

Name: Wilson Well Drilling, Inc.

Address: POB 729

Ruckersville VA 22968

Phone: 434-990-2010

Authorized Signature: \_\_\_\_\_

*Courtney M. Minko*

Date: 12/27/07 Representing: Wilson Well Drilling, Inc.

Virginia Contractors License Number: 2705028506

Commonwealth of Virginia  
Uniform Water Well Completion Report

Owner: Randy Baker Tax Map ID \_\_\_\_\_  
Address: \_\_\_\_\_ VDH Permit \_\_\_\_\_  
Phone: 434-953-5823 WWCB Permit \_\_\_\_\_  
Location: Rt 620 WWCB ID \_\_\_\_\_  
County \_\_\_\_\_

\* Well Data \*

General Information  
Drilling Method Air Rotary  
Depth to Bedrock 45  
Static Water Level \_\_\_\_\_  
Well Disinfected (Y or N) \_\_\_\_\_

Date Completed 7-6-19  
Yield 3 (GMP)  
Stabilized Water Level 285  
Disinfectant Used \_\_\_\_\_

Total Depth of Well 305  
Length of Test \_\_\_\_\_  
Natural Flow (Rate) \_\_\_\_\_  
Amount Used \_\_\_\_\_

Casing 1' Above To 47'  
Size 6 1/2 Material PVC  
Weight/Schedule 27.6

From \_\_\_\_\_ To \_\_\_\_\_  
Size \_\_\_\_\_ Material \_\_\_\_\_  
Weight/Schedule \_\_\_\_\_

From \_\_\_\_\_ To \_\_\_\_\_  
Size \_\_\_\_\_ Material \_\_\_\_\_  
Weight/Schedule \_\_\_\_\_

Gravel Pack  
From \_\_\_\_\_ To \_\_\_\_\_

From \_\_\_\_\_ To \_\_\_\_\_

From \_\_\_\_\_ To \_\_\_\_\_

Grout  
From 0 To 20'  
Bore Hole Size 10  
Type Renovate  
Method Four

From \_\_\_\_\_ To \_\_\_\_\_  
Bore Hole Size \_\_\_\_\_  
Type \_\_\_\_\_  
Method \_\_\_\_\_

From \_\_\_\_\_ To \_\_\_\_\_  
Bore Hole Size \_\_\_\_\_  
Type \_\_\_\_\_  
Method \_\_\_\_\_

Water Zones or Screened Intervals  
From 55 To 56  
Mesh Size \_\_\_\_\_ Diam \_\_\_\_\_  
From 85 To 89  
Mesh Size \_\_\_\_\_ Diam \_\_\_\_\_

From \_\_\_\_\_ To \_\_\_\_\_  
Mesh Size \_\_\_\_\_ Diam \_\_\_\_\_  
From \_\_\_\_\_ To \_\_\_\_\_  
Mesh Size \_\_\_\_\_ Diam \_\_\_\_\_

From \_\_\_\_\_ To \_\_\_\_\_  
Mesh Size \_\_\_\_\_ Diam \_\_\_\_\_  
From \_\_\_\_\_ To \_\_\_\_\_  
Mesh Size \_\_\_\_\_ Diam \_\_\_\_\_

\* Use Data \*

Private Well: Domestic  Agricultural \_\_\_\_\_ Industrial \_\_\_\_\_ Monitoring \_\_\_\_\_  
Public Well: Community \_\_\_\_\_ Non-community \_\_\_\_\_

\* Abandonment Information \*

Bored or Dug Wells  
Casing Removed, Y or N? \_\_\_\_\_  
If Y, Depth to which casing was removed: \_\_\_\_\_  
Depth and Type of Fill: \_\_\_\_\_  
Source of Fill \_\_\_\_\_  
Bentonite Plugs: From \_\_\_\_\_ to \_\_\_\_\_ From \_\_\_\_\_ to \_\_\_\_\_

Wells other than Bored Wells  
Casing removed, Y or N? \_\_\_\_\_  
Depth to which casing was removed: \_\_\_\_\_  
Applicable, depth(s), and type of gravel/sand fill: \_\_\_\_\_  
Source of gravel or sand: \_\_\_\_\_  
Cement: From \_\_\_\_\_ to \_\_\_\_\_ From \_\_\_\_\_ to \_\_\_\_\_

Method of permanently marking location: \_\_\_\_\_

RECEIVED

OCT 01 2019

Fluvanna County  
Health Department


BY: \_\_\_\_\_  
Facility Name: \_\_\_\_\_

\* Drillers Log \*

Depth

Description of Formation or Sediment

Remarks



(Use Additional Sheets if necessary)

I certify that the information contained here is true and that this well was installed and constructed in accordance with the permit and further that the well complies with all applicable state and local regulations, ordinances and laws.

Name Steven Leubner  
 Address 348 Gold Mine Rd Palmyra Va  
 Phone 434 987 9886  
 Drillers Signature [Signature]  
 Date 7-6-19 Representing IDE Drilling  
 Virginia Contractors License Number 2705073484

*[Faint, illegible text at the bottom of the page, possibly a stamp or additional notes.]*

6652 Rolling Rd. South

Commonwealth of Virginia  
Uniform Water Well Completion Report

Client I & J Home Builders/ Marlove  
Address 21708 James Madison Highway  
TCOY, VA 22974  
Phone 591-1100  
Location Baker Estate Rolling Rd 0.2 M. S  
of Blueberry Hill Lot 3

Tax Map ID 26(14)3  
VDM Permit 132-10-005  
VWCB Permit \_\_\_\_\_  
VWCB ID \_\_\_\_\_  
County Fluvanna

- Well Data -

General Information

Drilling Method Air Rotary  
Depth to Bedrock 9'  
Static Water Level 75' ± 120'  
Well Disinfectant (Year N) YES

Date Completed 7/2/10  
Yield 10 (GPM)  
Stabilized Water Level 30'  
Disinfectant Used Chlorine Tablets

Total Depth of Well 18.5'  
Length of Test 1 Hr  
Natural Flow (Rate) 10 GPM  
Amount Used 2 cups

Casing  
From 0 To 45'  
Size 4.5" Material PVC  
Weight/Schedule 40

From \_\_\_\_\_ To \_\_\_\_\_  
Size \_\_\_\_\_ Material \_\_\_\_\_  
Weight/Schedule \_\_\_\_\_

From \_\_\_\_\_ To \_\_\_\_\_  
Size \_\_\_\_\_ Material \_\_\_\_\_  
Weight/Schedule \_\_\_\_\_

Crown Pipe  
From \_\_\_\_\_ To \_\_\_\_\_

From \_\_\_\_\_ To \_\_\_\_\_

From \_\_\_\_\_ To \_\_\_\_\_

Gravel  
From 0 To 40'  
Base Hole Size 1 1/2"  
Type Bestonite  
Method pumped

From \_\_\_\_\_ To \_\_\_\_\_  
Base Hole Size \_\_\_\_\_  
Type \_\_\_\_\_  
Method \_\_\_\_\_

From \_\_\_\_\_ To \_\_\_\_\_  
Base Hole Size \_\_\_\_\_  
Type \_\_\_\_\_  
Method \_\_\_\_\_

Water Zones or Screened Intervals

From \_\_\_\_\_ To \_\_\_\_\_  
Mesh Size \_\_\_\_\_ Diam \_\_\_\_\_  
From \_\_\_\_\_ To \_\_\_\_\_  
Mesh Size \_\_\_\_\_ Diam \_\_\_\_\_

From \_\_\_\_\_ To \_\_\_\_\_  
Mesh Size \_\_\_\_\_ Diam \_\_\_\_\_  
From \_\_\_\_\_ To \_\_\_\_\_  
Mesh Size \_\_\_\_\_ Diam \_\_\_\_\_

From \_\_\_\_\_ To \_\_\_\_\_  
Mesh Size \_\_\_\_\_ Diam \_\_\_\_\_  
From \_\_\_\_\_ To \_\_\_\_\_  
Mesh Size \_\_\_\_\_ Diam \_\_\_\_\_

- Use Data -

Private Well: Domestic  Agricultural \_\_\_\_\_ Industrial \_\_\_\_\_ Monitoring \_\_\_\_\_  
Public Well: Community \_\_\_\_\_ Non Community \_\_\_\_\_

- Abandonment Information -

Board or Cap Wells  
Casing Removed, Y or N? \_\_\_\_\_  
If Y, Depth to which casing was removed: \_\_\_\_\_  
Depth and Type of Fill: \_\_\_\_\_  
Source of Fill \_\_\_\_\_  
Seepage Plug: From \_\_\_\_\_ to \_\_\_\_\_ From \_\_\_\_\_ to \_\_\_\_\_

Wells other than Board Wells  
Casing removed, Y or N? \_\_\_\_\_  
Depth to which casing was removed: \_\_\_\_\_  
Applicable, depth(s), and type of gravel(s) fill: \_\_\_\_\_  
Source of gravel or sand: \_\_\_\_\_  
Cement: From \_\_\_\_\_ to \_\_\_\_\_ From \_\_\_\_\_ to \_\_\_\_\_

Method of permanently marking location: \_\_\_\_\_

" Drillers Log "

Depth	Description of Formation or Sediment	Remarks
40'	Grout to Surface	
42'	Bedrock - Grey Shale	
45'	Bottom of Casing Borehole	
75'	Water Bearing Fracture zone	
120'	Water Bearing Fracture zone	
185'	Bottom of Borehole	

(Use additional Sheets if necessary)

I certify that the information contained here is true and that this well was installed and constructed in accordance with the permit and further that the well complies with all applicable state and local regulations, ordinances and laws.

Name Robert E. Tingley  
Address P.O. Box 6538  
Charlottesville Va 22906  
Phone 434-929-0123

Drillers Signature Robert E. Tingley  
Date 7/21/10 Representing CED, Inc.

Virginia Contractors License Number # 2705-020073

DPOR # 2719 000079

# 6692 Rolling Rd. South

Form GW-2  
Revised 7/1/2015  
Page 1 of 4

## COMMONWEALTH OF VIRGINIA UNIFORM WATER WELL COMPLETION REPORT

DEQ Well # \_\_\_\_\_  
USGS Local # \_\_\_\_\_  
VDH HDIN # 132-16-0010  
VDH PWSID # \_\_\_\_\_

### 1. Contact Information

Contact:	Name	Address	Phone
Owner	Rack Properties, LLC	902 Highland Drive <span style="float: right;">Howardsville VA 24562</span>	804-678-9508
Driller	Twin Creek Well Drilling Roger Luckado	2270 James River Rd. <span style="float: right;">Esmont VA, 22937</span>	434-987-4232
System Provider	2705-121-691		

### 2. Well Location

Physical Address: <u>adjacent to 6652 Rolling Rd.</u>		County/City: <u>Fluvanna</u>	
Subdivision Name: <u>J.R. Baker Estate</u>		Section:	Block: <u>6</u>
Tax Map/GPIN #: <u>26-14-3</u>		Well Designation or Number:	
Latitude:	N	Longitude:	W
Datum Source	Horizontal: <input type="checkbox"/> WGS84 <input type="checkbox"/> NAD83 <input type="checkbox"/> NAD27	Vertical: <input type="checkbox"/> NGVD29 <input type="checkbox"/> NAVD88	
Lat/Long Source (Check One): <input type="checkbox"/> Map <input type="checkbox"/> GPS <input type="checkbox"/> PPDGPS <input type="checkbox"/> Survey <input type="checkbox"/> Imagery <input type="checkbox"/> WASS			
Location Information Collected By :			
Physical Location Description:			

### 3. Facility & Use

Type of Facility (Check One):	Type of Use (Check All That Apply):		
<input type="checkbox"/> Waterworks	<input checked="" type="checkbox"/> Drinking/Domestic Use	<input type="checkbox"/> Food Processing	<input type="checkbox"/> Cooling/Heating
<input type="checkbox"/> Observation/Monitoring Well	<input type="checkbox"/> Agricultural	<input type="checkbox"/> Manufacturing	<input type="checkbox"/> Injection
<input checked="" type="checkbox"/> Private Well	<input type="checkbox"/> Irrigation	<input type="checkbox"/> Fire Safety	<input type="checkbox"/> Geothermal

### 4. Well Construction

Well designation, Name or Number:			
Date Started: <u>3-23-16</u>	Date Completed: <u>3-31-16</u>	Type Rig: <u>Churn</u>	
Class Well (Check One): <input type="checkbox"/> I <input type="checkbox"/> IIA <input type="checkbox"/> IIB <input type="checkbox"/> IIIA <input type="checkbox"/> IIIB <input checked="" type="checkbox"/> IIIC <input type="checkbox"/> IIID <input type="checkbox"/> IIIE <input type="checkbox"/> IV			
Construction Type (Check One): <input checked="" type="checkbox"/> New <input type="checkbox"/> Existing-Modified			
Well Depth: <u>100</u> ft.	Borehole Depth: <u>20</u> ft.	Depth to Bedrock: <u>40</u> ft.	
Hole Size (Include reamed zones): <u>10</u> inches from <u>0</u> to <u>20</u> ft. <u>6 1/8</u> inches from <u>20</u> to <u>100</u> ft.			
Height of Casing above Land Surface: <u>2</u> ft. inches			
Casing Size (I.D.) and Materials: (below)		Total Depth of Casing: <u>47</u> ft.	
<u>6 1/4</u> inches from <u>2</u> ft. to <u>47</u> ft.	Material <u>PVC</u>	Weight per ft. <u>27.6</u>	or wall thickness in.
inches from to ft.	Material	Weight per ft.	or wall thickness in.
inches from to ft.	Material	Weight per ft.	or wall thickness in.
inches from to ft.	Material	Weight per ft.	or wall thickness in.
inches from to ft.	Material	Weight per ft.	or wall thickness in.
Screen Size & Mesh:			
inches from to ft.	Mesh Size	Type	
inches from to ft.	Mesh Size	Type	
inches from to ft.	Mesh Size	Type	
Water Zones: from <u>50</u> ft. to <u>too much water to know</u> ft. from to ft. from to ft.			
Gravel Pack: from to ft. from to ft. from to ft.			
Grout Type: from <u>surface</u> to <u>20</u> ft.		Grouting Method: <u>Pour</u>	Type of Seal: <u>Bentonite</u>
This information was collected by Camera Survey: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			Date Conducted:
Additional Well Construction Form Information Attached: <input type="checkbox"/> Yes <input type="checkbox"/> No			



COMMONWEALTH OF VIRGINIA  
 UNIFORM WATER WELL COMPLETION REPORT

DEQ Well # \_\_\_\_\_  
 USGS Local # \_\_\_\_\_  
 VDH HDIN # 132-16-0010  
 VDH PWSID # \_\_\_\_\_

Well designation, Name or Number: \_\_\_\_\_

**5. Disinfection**

Well Disinfected:  Yes  No | Date: \_\_\_\_\_

**6. Abandonment** (\*When abandoning a well, Sections 1 thru 6 are required to be completed)

Date Started:	Date Completed:	Type Rig:
Static Water Level (unpumped level measured): _____ ft.		
Casing Size (I.D.) and Materials:	Casing Pulled: <input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Uncased Well	
Depth of Fill:	Type and Source of Fill:	
Grout: From _____ to _____ Type: _____	From _____ to _____	Type: _____
Method of permanently marking location: _____		

**7. Pump Test**

Static Water Level (unpumped level measured):	<u>17</u> ft.		
Date: <u>3-31-16</u>	Method (Check One):	<input checked="" type="checkbox"/> Water Tape	<input type="checkbox"/> Airline <input type="checkbox"/> Transducer <input type="checkbox"/> Other
Stabilized measured pumping water level:	<u>22</u> ft.		
Date: <u>3-31-16</u>	Method (Check One):	<input type="checkbox"/> Top of Well <input type="checkbox"/> Top of Casing	<input checked="" type="checkbox"/> Surface Level
Test Pump Intake Depth: _____ ft	Stabilized Yield:	_____ gpm after _____ hours	
Natural Flow: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Flow Rate <u>20+</u> gpm		

**8. Pump Data**

Type:	Motor HP:
Production Pump Intake Depth: _____ ft	Rated Capacity: _____ gpm at _____ ft TDH

**9. Geologic Information**

Formation:	Type Logs:
Lithology:	Cuttings:
Province:	Aquifer Test Performed:
Geologic Map Used:	
Water Quality Results Attached: Yes _____ No _____	

**Comments:**

COMMONWEALTH OF VIRGINIA  
 UNIFORM WATER WELL COMPLETION REPORT

DEQ Well # \_\_\_\_\_  
 USGS Local # \_\_\_\_\_  
 VDH HDIN # 132-16-0010  
 VDH PWSID # \_\_\_\_\_

10. Driller's Log (Use additional sheets if necessary)

Well designation, Name or Number:					
Depth (feet)		Type of Rock or Soil	Remarks	Drilling Time (Min.)	Diagram of Well Construction (with dimensions)
From	To	(Color, material, fossils, hardness, etc.)	(Water, caving, cavities, etc.)		
0	10'	Redish Brown Dirt			Water tight Seal
10'	40'	Brown Dirt/white rock & shale mixture			Ground Surface
40'	100'	Rock Blue/white mixture			0-10' Redish Brown Dirt
			Set Casing 47'		10'-40' Brown Dirt/Rock mix.
					Set Casing 47'
					40'-100' Rock-Blue/white mix
					T.D. 100'

I certify that the information contained herein is true and correct and that this well and/or system has been installed and constructed in accordance with the applicable permit and further that the well complies with all applicable federal, state and local regulations, ordinances and laws.

Signature: Roger Luckado Date: 3-31-16

License Number: 2705-121-691

WATER WELL COMPLETION REPORT

BWCM No.

(Certification of Completion/County Permit)

State Water Control Board  
P. O. Box 11143  
2111 North Hamilton St.  
Richmond, Va. 23230

County/City

FLUVANNH

County/City Stamp

SWCB Permit
County Permit
Certification of inspecting official: This well does _____ does not meet code/low requirements. S. _____ Date _____
For Office Use

• Virginia Plane Coordinates

N \_\_\_\_\_  
E \_\_\_\_\_  
Latitude & Longitude  
N \_\_\_\_\_  
W \_\_\_\_\_

• Topo. Map No. \_\_\_\_\_  
• Elevation \_\_\_\_\_ ft.  
• Formation \_\_\_\_\_  
• Lithology \_\_\_\_\_  
• River Basin \_\_\_\_\_  
• Province \_\_\_\_\_  
• Type Logs \_\_\_\_\_  
• Cuttings \_\_\_\_\_  
• Water Analysis \_\_\_\_\_  
• Aquifer Test \_\_\_\_\_

• Owner RALPH BAKER

• Well Designation or Number  
Address RT 2  
SCOTTSVILLE, VA  
Phone 286-2569

• Drilling Contractor TUCKER HILL DRILLING  
Address RT 2 BOX 154  
SCOTTSVILLE, VA 24590  
Phone 589-8715

• Tax Map I.D. No. \_\_\_\_\_  
Subdivision \_\_\_\_\_  
Section \_\_\_\_\_  
Block \_\_\_\_\_  
Lot \_\_\_\_\_  
Class Well: I \_\_\_\_\_ IIA \_\_\_\_\_  
IIB \_\_\_\_\_ IIIA \_\_\_\_\_ IIIB \_\_\_\_\_  
IIIC \_\_\_\_\_ IIID \_\_\_\_\_ IIIE \_\_\_\_\_

WELL LOCATION: 500 (feet/miles SOUTH direction) of INTER. OF SK. 1620 + 619  
and \_\_\_\_\_ (feet/miles \_\_\_\_\_ direction) of \_\_\_\_\_  
(If possible please include map showing location marked)

Date started 3/6/87 • Date completed 3/13/87 Type rig CABLE TOOL

I. WELL DATA: New  Reworked \_\_\_\_\_ Deepened \_\_\_\_\_

• Total depth 83 ft.  
• Depth to bedrock 54 ft.

• Hole size (Also include reamed zones)

• <u>8</u> inches from <u>0</u> to <u>54</u> ft.
• <u>6.25</u> inches from <u>55</u> to <u>83</u> ft.
• _____ inches from _____ to _____ ft.

• Casings size (I.D.) and material

• <u>6.25</u> inches from <u>0</u> to <u>54</u> ft.
Material <u>PVC</u>
Wt. per foot _____ or wall thickness <u>.25</u> in.
• _____ inches from _____ to _____ ft.
Material _____
Wt. per foot _____ or wall thickness _____ in.
• _____ inches from _____ to _____ ft.
Material _____
Wt. per foot _____ or wall thickness _____ in.

• Screen size and mesh for each zone (where applicable)

• _____ inches from _____ to _____ ft.
• Mesh size _____ Type _____
• _____ inches from _____ to _____ ft.
• Mesh size _____ Type _____
• _____ inches from _____ to _____ ft.
• Mesh size _____ Type _____
• _____ inches from _____ to _____ ft.
• Mesh size _____ Type _____

• Gravel pack

• From <u>54</u> to <u>30</u> ft.
• From _____ to _____ ft.

• Grout

• From <u>30</u> to <u>0</u> ft. Type <u>PORTLAND CEM.</u>
• From _____ to _____ ft. Type _____

2. WATER DATA • Water temperature 52° of \_\_\_\_\_

• Static water level (unpumped level-measured) 40 ft.  
• Stabilized measured pumping water level \_\_\_\_\_ ft.  
• Stabilized yield 115 gpm after 24 hours  
Natural Flow: Yes  No \_\_\_\_\_ flow rate: 115 gpm  
Comment on quality VERY GOOD

3. WATER ZONES: From 59 To 60  
From 65 To 70 From \_\_\_\_\_ To \_\_\_\_\_  
From \_\_\_\_\_ To \_\_\_\_\_ From \_\_\_\_\_ To \_\_\_\_\_

4. USE DATA:

Type of use: Drinking  Livestock Watering \_\_\_\_\_  
Irrigation \_\_\_\_\_ Food processing \_\_\_\_\_ Household \_\_\_\_\_  
Manufacturing \_\_\_\_\_ Fire safety \_\_\_\_\_ Cleaning \_\_\_\_\_  
Recreation \_\_\_\_\_ Aesthetic \_\_\_\_\_ Cooling or heating \_\_\_\_\_  
Injection \_\_\_\_\_ Other \_\_\_\_\_

• Type of facility: Domestic  Public water supply \_\_\_\_\_  
Public institution \_\_\_\_\_ Farm \_\_\_\_\_ Industry \_\_\_\_\_  
Commercial \_\_\_\_\_ Other \_\_\_\_\_

5. PUMP DATA: Type SUB • Rated H.P. 1/2  
• Intake depth 75 • Capacity \_\_\_\_\_ at \_\_\_\_\_ head

6. WELLHEAD: Type well seal CAP  
Pressure tank 18 gal., Loc. CRAWL SPACE  
Sample tap \_\_\_\_\_ Measurement port \_\_\_\_\_  
Well vent \_\_\_\_\_ Pressure relief valve \_\_\_\_\_  
Gate valve \_\_\_\_\_ Check valve (when required) \_\_\_\_\_  
Electrical disconnect switch on power supply \_\_\_\_\_

\* 7. DISINFECTION: Well disinfected  yes \_\_\_\_\_ no \_\_\_\_\_  
Date \_\_\_\_\_ Disinfectant used BLENCH  
Amount 1/2 GAL Hours used 24

8. ABANDONMENT (where applicable) • yes \_\_\_\_\_ no \_\_\_\_\_  
Casing pulled yes \_\_\_\_\_ no \_\_\_\_\_ not applicable \_\_\_\_\_  
Plugging grout From \_\_\_\_\_ to \_\_\_\_\_ material \_\_\_\_\_

\* WILL BE DISINFECTED AT  
OVER TIME OF PUMP INSTALL.

Owner

KALPH BAKER

BWCM No.

9. State law requires submitting to the Virginia State Water Control Board information about groundwater and wells for every well made in the State intended for water, or any other non-exempt well. This information must be submitted whether the well is completed, on standby, or abandoned. Information required includes: an accurately and completely prepared water well completion report, full data from any aquifer pumping tests, drill cuttings taken at ten foot intervals (unless exemption is secured), the results of any chemical analyses, and copies of any geophysical logs. Quarterly pumpage and use reports are required from owners of public supply and industrial wells. County or State permits to drill may be required in some parts of the state. Some counties require submission of a water well completion report. The Virginia State Health Department requires a water well completion report for public supply wells.

10. DRILLERS LOG (use additional Sheets if necessary)

11.

12. DIAGRAM OF WELL CONSTRUCTION (with dimensions)

DEPTH (feet)		TYPE OF ROCK OR SOIL	REMARKS	Drilling Time (Min.)
From	To	(color, material, fossils, hardness, etc.)	(water, caving, cavities, broken, core, shot, (etc.))	
0	25	RED SOIL, SOFT	NO CAVING	120
26	34	BROWN SOIL, SOFT	NO WATER NO CAVING	60
35	53	SAND, VERY SOFT	CAVING + LITTLE WATER	4 HRS
54	65	WHITE FLINT + GRAY SLATE MIXED HARD	GOOD VEINS + NO CAVING	6 HRS
66	83	GRAYISH SLATE OR SHALE, HARD	SOME WATER	8 HRS

13. Well lot dedicated? NO Size 1 ft. X 1 ft. Well house? NO  
 Distance to nearest pollutant source 1100 ft. Type SEPTIC  
 Distance to nearest property line 15 ft. Building \_\_\_\_\_ ft.

14. WATER SERVICE PIPE: Checked under \_\_\_\_\_ p.s.i. for \_\_\_\_\_  
 minutes. Pipe size 1 inches. Material BLACK ROLL  
 Installer T HICKK K WELL DRILLING  
 Date \_\_\_\_\_

15. I certify that the information contained herein is true and correct and that this well and/or system has been installed and constructed in accordance with the requirements for well construction as specified in compliance with appropriate county or independent city ordinances and the laws and rules of the Commonwealth of Virginia.

Signature Ronald S. Wicker (Seal), Date 3/17/87  
 (Well driller or authorized person)

License No. 034489

State Water Control Board Regional Offices

Valley Reg. Off.  
 116 North Main Street  
 P. O. Box 268  
 Bridgewater, Va. 22812  
 703-828-2595

Piedmont Reg. Off.  
 4010 West Broad Street  
 P. O. Box 6616  
 Richmond, Va. 23230  
 804-257-1006

Southwest Reg. Off.  
 408 East Main Street  
 P. O. Box 476  
 Abingdon, Va. 24210  
 703-628-5183

Tidewater Reg. Off.  
 287 Pembroke Office Park  
 Suite 310 Pembroke No. 2  
 Va. Beach, Va. 23462  
 804-499-8742

West Central Reg. Off.  
 Executive Park  
 3312 Peters Creek Road  
 Roanoke, Va. 24019  
 703-982-7432

Northern Virginia Reg. Off.  
 5515 Cherokee Avenue  
 Suite 404  
 Alexandria, Va. 22312  
 703-750-9111

WATER WELL COMPLETION REPORT

• BWCM No. \_\_\_\_\_

(Certification of Completion/County Permit)

State Water Control Board  
P. O. Box 11143  
2111 North Hamilton St.  
Richmond, Va. 23230

County/City

FLUVANNA

County/City Stamp

SWCB Permit	_____
County Permit	_____
Certification of inspecting official: This well does _____ does not meet code/low requirements. S. _____ Date _____	
For Office Use	

• Virginia Plane Coordinates  
N \_\_\_\_\_  
E \_\_\_\_\_  
Latitude & Longitude  
N \_\_\_\_\_  
W \_\_\_\_\_

• Topo. Map No. \_\_\_\_\_  
• Elevation \_\_\_\_\_ ft.  
• Formation \_\_\_\_\_  
• Lithology \_\_\_\_\_  
• River Basin \_\_\_\_\_  
• Province \_\_\_\_\_  
• Type Logs \_\_\_\_\_  
• Cuttings \_\_\_\_\_  
• Water Analysis \_\_\_\_\_  
• Aquifer Test \_\_\_\_\_

• Owner RALPH BAKER  
• Well Designation or Number \_\_\_\_\_  
Address RT 2  
SCOTTSVILLE, VA.  
Phone 2916-3564

• Drilling Contractor THACKERS WELL DRILLING  
Address RT 2 BOX 154  
SCOTTSVILLE VA 24590  
Phone 904-599-8915

Tax Map I.D. No. \_\_\_\_\_  
Subdivision \_\_\_\_\_  
Section \_\_\_\_\_  
Block \_\_\_\_\_  
Lot \_\_\_\_\_  
Class Well: I \_\_\_\_\_ IIA \_\_\_\_\_  
IIB \_\_\_\_\_ IIIA \_\_\_\_\_ IIIB \_\_\_\_\_  
IIIC \_\_\_\_\_ IIID \_\_\_\_\_ IIIE \_\_\_\_\_

WELL LOCATION: 800 (feet/miles SOUTH direction) of INTER OF SR 1620+1619  
and \_\_\_\_\_ feet/miles \_\_\_\_\_ (direction) of \_\_\_\_\_  
(If possible please include map showing location marked)

Date started 3/20/87 • Date completed 3/27/87 Type rig CABLE TOOL

1. WELL DATA: New  Reworked \_\_\_\_\_ Deepened \_\_\_\_\_

• Total depth 98 ft.  
• Depth to bedrock 40 FT ft.  
• Hole size (Also include reamed zones)  
• 8 inches from 0 to 40 ft.  
• 6.25 inches from 41 to 98 ft.  
• \_\_\_\_\_ inches from \_\_\_\_\_ to \_\_\_\_\_ ft.

• Casing size (I.D.) and material  
• 6.25 inches from 0 to 40 ft.  
Material PVC  
Wt. per foot \_\_\_\_\_ or wall thickness .25 in.  
• \_\_\_\_\_ inches from \_\_\_\_\_ to \_\_\_\_\_ ft.  
Material \_\_\_\_\_  
Wt. per foot \_\_\_\_\_ or wall thickness \_\_\_\_\_ in.  
• \_\_\_\_\_ inches from \_\_\_\_\_ to \_\_\_\_\_ ft.  
Material \_\_\_\_\_  
Wt. per foot \_\_\_\_\_ or wall thickness \_\_\_\_\_ in.

• Screen size and mesh for each zone (where applicable)  
• \_\_\_\_\_ inches from \_\_\_\_\_ to \_\_\_\_\_ ft.  
• Mesh size \_\_\_\_\_ Type \_\_\_\_\_  
• \_\_\_\_\_ inches from \_\_\_\_\_ to \_\_\_\_\_ ft.  
• Mesh size \_\_\_\_\_ Type \_\_\_\_\_  
• \_\_\_\_\_ inches from \_\_\_\_\_ to \_\_\_\_\_ ft.  
• Mesh size \_\_\_\_\_ Type \_\_\_\_\_  
• \_\_\_\_\_ inches from \_\_\_\_\_ to \_\_\_\_\_ ft.  
• Mesh size \_\_\_\_\_ Type \_\_\_\_\_

• Gravel pack  
• From 40 to 35 ft.  
• From \_\_\_\_\_ to \_\_\_\_\_ ft.

• Grout  
• From 35 to 0 ft. Type PORTLAND CEM.  
• From \_\_\_\_\_ to \_\_\_\_\_ ft. Type \_\_\_\_\_

2. WATER DATA • Water temperature 52° OF  
• Static water level (unpumped level-measured) 45 ft.  
• Stabilized measured pumping water level \_\_\_\_\_ ft.  
• Stabilized yield 115 gpm after 24 hours  
Natural Flow: Yes  No \_\_\_\_\_ flow rate: 115 gpm  
Comment on quality VERY GOOD

3. WATER ZONES: From 51 To 55  
From 60 To 63 From 70 To 72  
From \_\_\_\_\_ To \_\_\_\_\_ From \_\_\_\_\_ To \_\_\_\_\_

4. USE DATA:  
Type of use: Drinking  Livestock Watering \_\_\_\_\_  
Irrigation \_\_\_\_\_ Food processing \_\_\_\_\_ Household \_\_\_\_\_  
Manufacturing \_\_\_\_\_ Fire safety \_\_\_\_\_ Cleaning \_\_\_\_\_  
Recreation \_\_\_\_\_ Aesthetic \_\_\_\_\_ Cooling or heating \_\_\_\_\_  
Injection \_\_\_\_\_ Other \_\_\_\_\_

• Type of facility: Domestic  Public water supply \_\_\_\_\_  
Public institution \_\_\_\_\_ Farm \_\_\_\_\_ Industry \_\_\_\_\_  
Commercial \_\_\_\_\_ Other \_\_\_\_\_

5. PUMP DATA: Type SUB • Rated H.P. 3/4  
• Intake depth 90 • Capacity \_\_\_\_\_ at \_\_\_\_\_ head

6. WELLHEAD: Type well seal CAP  
Pressure tank 18 gal. Loc. HOUSE (CRAWL)  
Sample tap \_\_\_\_\_ Measurement port \_\_\_\_\_  
Well vent  Pressure relief valve \_\_\_\_\_  
Gate valve \_\_\_\_\_ Check valve (when required) \_\_\_\_\_  
Electrical disconnect switch on power supply \_\_\_\_\_

\*7. DISINFECTION: Well disinfected  yes \_\_\_\_\_ no \_\_\_\_\_  
Date \_\_\_\_\_ Disinfectant used BLEACH  
Amount 1/2 GAL Hours used 24

8. ABANDONMENT (where applicable) • yes \_\_\_\_\_ no \_\_\_\_\_  
Casing pulled yes \_\_\_\_\_ no \_\_\_\_\_ not applicable \_\_\_\_\_  
Plugging grout From \_\_\_\_\_ to \_\_\_\_\_ material \_\_\_\_\_

\*WILL BE DISINFECTED AT  
OVERTIME OF PUMP INSTALL.

Owner RALPH LUKER

BWCM No. \_\_\_\_\_

9. State law requires submitting to the Virginia State Water Control Board information about groundwater and wells for every well made in the State intended for water, or any other non-exempt well. This information must be submitted whether the well is completed, on standby, or abandoned. Information required includes: an accurately and completely prepared water well completion report, full data from any aquifer pumping tests, drill cuttings taken at ten foot intervals (unless exemption is secured), the results of any chemical analyses, and copies of any geophysical logs. Quarterly pumpage and use reports are required from owners of public supply and industrial wells. County or State permits to drill may be required in some parts of the state. Some counties require submission of a water well completion report. The Virginia State Health Department requires a water well completion report for public supply wells.

10. DRILLERS LOG (use additional Sheets if necessary)				11.	12. DIAGRAM OF WELL CONSTRUCTION (with dimensions)
DEPTH (feet)		TYPE OF ROCK OR SOIL	REMARKS	Drilling Time (Min.)	
From	To	(color, material, fossils, hardness, etc.)	(water, caving, cavities, broken, core, shot, (etc.))		
0	19	REDDISH ORANGE SOIL	NO WATER NO CAVING	2 HRS	
20	40	BROWN SHALE SOFT	NO WATER NO CAVING	3 HRS	
41	52	WHITE FLINT + BROWN SHALE MIX FAIRLY HARD	LITTLE WATER	4 HRS	
53	82	SHALE (BROWN) FAIRLY HARD	MUCH WATER NO CAVING	10 HRS	
83	98	WHITE FLINT + BLUE STONE	LITTLE WATER	8 HRS	

13. Well lot dedicated? NO; Size \_\_\_\_\_ ft. X \_\_\_\_\_ ft.; Well house? NO  
 Distance to nearest pollutant source 100 ft., Type FIELD LINE  
 Distance to nearest property line 25 ft., Building 100 ft.

14. WATER SERVICE PIPE: Checked under \_\_\_\_\_ p.s.i. for \_\_\_\_\_ minutes. Pipe size 1 inches, Material BLACK PULL  
 Installer LUKER WELLS DRILLING  
 Date \_\_\_\_\_

15. I certify that the information contained herein is true and correct and that this well and/or system has been installed and constructed in accordance with the requirements for well construction as specified in compliance with appropriate county or independent city ordinances and the laws and rules of the Commonwealth of Virginia.

**State Water Control Board Regional Offices**

- Valley Reg. Off.  
116 North Main Street  
P. O. Box 268  
Bridgewater, Va. 22812  
703-828-2595
- Southwest Reg. Off.  
408 East Main Street  
P. O. Box 476  
Abingdon, Va. 24210  
703-628-5183
- West Central Reg. Off.  
Executive Park  
5312 Peters Creek Road  
Roanoke, Va. 24019  
708-982-7432
- Piedmont Reg. Off.  
4010 West Broad Street  
P. O. Box 6616  
Richmond, Va. 23230  
804-257-1006
- Tidewater Reg. Off.  
287 Pembroke Office Park  
Suite 310 Pembroke No. 2  
Va. Beach, Va. 23462  
804-499-8742
- Northern Virginia Reg. Off.  
5515 Cherokee Avenue  
Suite 404  
Alexandria, Va. 22312  
703-750-9111

Signature [Signature] (Seal, Date 3/29/17)  
 License No. 034449

COMMONWEALTH OF VIRGINIA  
WATER WELL COMPLETION REPORT  
(Certification of Completion/County Permit)

7022 Rolling Rd. South

State Water Control Board  
P. O. Box 11143  
2111 North Hamilton St.  
Richmond, Va. 23230

County/City

Hughes Fluvanna

County/City Stamp

SWCB Permit
County Permit
Certification of inspecting official
This well does <input checked="" type="checkbox"/> does not <input type="checkbox"/>
meet code/low requirements
S
Date
For Office Use

Virginia Plane Coordinates

N \_\_\_\_\_

E \_\_\_\_\_

Latitude & Longitude

N \_\_\_\_\_

W \_\_\_\_\_

Topo. Map No. \_\_\_\_\_

Elevation \_\_\_\_\_ ft.

Formation \_\_\_\_\_

Lithology \_\_\_\_\_

River Basin \_\_\_\_\_

Province \_\_\_\_\_

Type Logs \_\_\_\_\_

Cuttings \_\_\_\_\_

Water Analysis \_\_\_\_\_

Aquifer Test \_\_\_\_\_

Owner Jefferson Area Builders

Well Designation or Number \_\_\_\_\_

Address 310 Jurns Court  
Charlottesville, Va. 22901

Phone \_\_\_\_\_

Drilling Contractor FRED JONES WELL CO.

Address P. O. Box 818 Appomattox, Va. 24522

Phone Phone 352-7872

Tax Map I. D. No.
Subdivision
Section
Block
Lot
Class Well I _____ IIA _____
IIA _____ IIIB _____
IIIC _____ IIID _____ IIIE _____

WELL LOCATION: \_\_\_\_\_ (feet/miles 0 direction) of Rt. 620

and \_\_\_\_\_ feet/miles (direction) of \_\_\_\_\_

(If possible please include map showing location marked)

Date started 12-28-87 Date completed 1-15-88 Type rig Hyd Boring

WELL DATA: New  Reworked \_\_\_\_\_ Deepened \_\_\_\_\_

Total depth 60 ft.

Depth to bedrock 59 ft.

Hole size (Also include reamed zones)

30 inches from 0 to 59 ft.

Casing size (I.D.) and material

24 inches from 0 to 60 ft.

Material Concrete

Wt. per foot \_\_\_\_\_ or wall thickness \_\_\_\_\_ in.

Material \_\_\_\_\_

Wt. per foot \_\_\_\_\_ or wall thickness \_\_\_\_\_ in.

Material \_\_\_\_\_

Wt. per foot \_\_\_\_\_ or wall thickness \_\_\_\_\_ in.

Material \_\_\_\_\_

Screen size and mesh for each zone (where applicable)

Mesh size \_\_\_\_\_ Type \_\_\_\_\_

Gravel pack

From \_\_\_\_\_ to \_\_\_\_\_ ft.

Grout

From 0 to 20 ft. Type poured w/ pipe

2. WATER DATA Water temperature \_\_\_\_\_ OF

Static water level (unpumped level) measured \_\_\_\_\_ ft.

Stabilized measured pumping water level \_\_\_\_\_ ft.

Stabilized yield \_\_\_\_\_ gpm after \_\_\_\_\_ hours

Natural Flow Yes  No \_\_\_\_\_ flow rate 20' water gpm

Comment on quality \_\_\_\_\_

3. WATER ZONES: From \_\_\_\_\_ To \_\_\_\_\_

From \_\_\_\_\_ To \_\_\_\_\_ From \_\_\_\_\_ To \_\_\_\_\_

From \_\_\_\_\_ To \_\_\_\_\_ From \_\_\_\_\_ To \_\_\_\_\_

4. USE DATA

Type of use: Drinking  Livestock Watering \_\_\_\_\_

Irrigation \_\_\_\_\_ Food processing \_\_\_\_\_ Household

Manufacturing \_\_\_\_\_ Fire safety \_\_\_\_\_ Cleaning \_\_\_\_\_

Recreation \_\_\_\_\_ Aesthetic \_\_\_\_\_ Cooling or heating \_\_\_\_\_

Injection \_\_\_\_\_ Other \_\_\_\_\_

Type of facility: Domestic  Public water supply \_\_\_\_\_

Public institution \_\_\_\_\_ Farm \_\_\_\_\_ Industry \_\_\_\_\_

Commercial \_\_\_\_\_ Other \_\_\_\_\_

5. PUMP DATA: Type sub Rated H.P. 1/2

Intake depth 54 Capacity \_\_\_\_\_ at \_\_\_\_\_ head

6. WELLHEAD: Type well seal \_\_\_\_\_

Pressure tank 40 gal. Loc. house

Sample tap \_\_\_\_\_ Measurement port \_\_\_\_\_

Well vent \_\_\_\_\_ Pressure relief valve \_\_\_\_\_

Gate valve \_\_\_\_\_ Check valve (when required) \_\_\_\_\_

Electrical disconnect switch on power supply \_\_\_\_\_

7. DISINFECTION: Well disinfected  yes \_\_\_\_\_ no \_\_\_\_\_

Date \_\_\_\_\_ Disinfectant used \_\_\_\_\_

Amount \_\_\_\_\_ Hours used \_\_\_\_\_

8. ABANDONMENT (where applicable) yes \_\_\_\_\_ no \_\_\_\_\_

Casing pulled yes \_\_\_\_\_ no \_\_\_\_\_ not applicable \_\_\_\_\_

Plugging grout From \_\_\_\_\_ to \_\_\_\_\_ material \_\_\_\_\_

D. State law requires submitting to the Virginia State Water Control Board information about groundwater and wells for every well made in the State intended for water, or any other non-exempt well. This information must be submitted whether the well is completed, on standby, or abandoned. Information required includes: an accurately and completely prepared water well completion report, full data from any aquifer pumping tests, drill cuttings taken at ten foot intervals (unless exemption is secured), the results of any chemical analyses, and copies of any geophysical logs. Quarterly pumpage and use reports are required from owners of public supply and industrial wells. County or State permits to drill may be required in some parts of the state. Some counties require submission of a water well completion report. The Virginia State Health Department requires a water well completion report for public supply wells.

10. DRILLERS LOG (use additional Sheets if necessary)

10. DRILLERS LOG (use additional Sheets if necessary)			11	12. DIAGRAM OF WELL CONSTRUCTION (with dimensions)
DEPTH (feet)		TYPE OF ROCK OR SOIL (color, material, fossils, hardness, etc.)	REMARKS (water, caving, cavities, broken, core, shot, etc.)	Drilling Time (Min.)
From	To			
0	59	hard	Well Complete	

13. Well lot dedicated? \_\_\_\_\_ Size \_\_\_\_\_ ft. X \_\_\_\_\_ ft. Well house? \_\_\_\_\_  
 Distance to nearest pollutant source \_\_\_\_\_ ft. Type \_\_\_\_\_  
 Distance to nearest property line \_\_\_\_\_ ft. Building \_\_\_\_\_ ft.

14. WATER SERVICE PIPE Checked under \_\_\_\_\_ p. s. i. for \_\_\_\_\_  
 minutes. Pipe size \_\_\_\_\_ inches. Material \_\_\_\_\_  
 Installer \_\_\_\_\_  
 Date \_\_\_\_\_

15. I certify that the information contained herein is true and correct and that this well and/or system has been installed and constructed in accordance with the requirements for well construction as specified in compliance with appropriate county or independent city ordinances and the laws and rules of the Commonwealth of Virginia.

State Water Control Board Regional Offices

Valley Reg. Off.  
 116 North Main Street  
 P. O. Box 268  
 Bridgewater, Va. 22012  
 703-820-2595

Southwest Reg. Off.  
 400 East Main Street  
 P. O. Box 476  
 Abingdon, Va. 24210  
 703-620-5183

West Central Reg. Off.  
 Executive Park  
 3312 Peters Creek Road  
 Roanoke, Va. 24019  
 703-902-7432

Piedmont Reg. Off.  
 4010 West Broad Street  
 P. O. Box 6616  
 Richmond, Va. 23230  
 804-257-1006

Tidewater Reg. Off.  
 287 Pembroke Office Park  
 Suite 310 Pembroke No. 2  
 Va. Beach, Va. 23462  
 804-499-8742

Northern Virginia Reg. Off.  
 5515 Cherokee Avenue  
 Suite 404  
 Alexandria, Va. 22312  
 703-750-9111

Signature Fred Jones Well Co. (Seal) Date 1-15-88  
 (Well driller or authorized person) Doc  
 License No. \_\_\_\_\_